


DETECTOR LOOP REQUIREMENTS AND CALCULATIONS
FOR IL 203 & MADISON AVE.

LOOP#	PHASE #	LOOP SIZE (FT. X FT.)	REQUIRED # OF TURNS	CALCULATED INDUCTANCE MICROHENRIES	CALCULATED RESISTANCE OHMS
1. EB LT CD	4	6 X 50-0	3-6-3	835.9	2.7
2. EB THRU CD	4	6 X 50-0	3-6-3	1006.0	6.6
3. EB RT CD A	4	6 X 30-0	3-6-3	534.2	2.1
4. EB RT CD B	4	6 X 50-0	3-6-3	827.1	2.5
5. NB THRU & LT CD	1 & 6	6 X 50-0	3-6-3	837.5	2.8
6. WB THRU CD	3	6 X 50-0	3-6-3	819.4	2.4
7. SB THRU & LT CD	2 & 5	6 X 50-0	3-6-3	798.8	1.9

THE ABOVE VALUES ARE CALCULATED OF COMBINED LOOP AND LEAD-IN INDUCTANCE AND RESISTANCE. ACTUAL MEASURED VALUES SHOULD BE WITHIN +/- 20% OF THESE VALUES.


O=QUADRAPOLE

⊙=SEE DETAIL A



IL 203 & MADISON AVE.

△ REVISED SHEET 7-23-14



FILE NAME: c:\pwwork\avidot\prastanne\08332803\0875g24.sht-TS.dgn	USER NAME: prastanne	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DETECTOR LOOP REPLACEMENT & ADA T.S. MODIFICATION PLAN 1 OF 5	F.A.P. RTE.: 594	SECTION: 0X-3,X-2JRS-1	COUNTY: MADISON	TOTAL SHEETS: 52	SHEET NO.: 46	
PLOT SCALE: 50.0000' / 1"	CHECKED: -	REVISED: -	SCALE: 1" = 50'			SHEET NO. 2 OF 7 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT			
PLOT DATE: 5/28/2014	DATE: -	REVISED: -									