

CONSTR. CODE
 80% FEDERAL
 20% STATE
 ROADWAY
 0005
 URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	73	73
60608300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	27	27
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	162.5	162.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5867	5867

* SPECIALTY ITEMS

FILE NAME =	USER NAME = ghallandesko	DESIGNED -	REVISED -
o:\p\work\p\p\ghallandesko\08332083	0876024-shl-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100,0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 5/9/2014	DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
604	IX-3, X-2IRS-1	MADISON	52	6
CONTRACT NO. 76624				
SCALE: N/A	SHEET	OF	SHEETS	STA. TO STA.
ILLINOIS FED. AID PROJECT				