

**PORTLAND CEMENT CONCRETE
ALTERNATE BID B**

LOCATION STATION TO STATION	DESCRIPTION	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE SHOULDERS 8"
		SQ YD	SQ YD	SQ YD	SQ YD
STAGE 1A					
U.S. 45					
449+88 TO 478+00		65,541	73,145	85,541	
449+88 TO 482+39	Outside Shld.			3,635	3,635
482+81 TO 515+69	Outside Shld.			3,270	3,270
516+48 TO 576+73	Outside Shld.			6,872	6,872
577+31 TO 605+11	Outside Shld.			3,180	3,180
605+69 TO 640+00	Outside Shld.			4,668	4,668
649+88 TO 678+00	Outside Shld.			3,138	3,138
481+53 TO 482+05	Inside Shld.			1,348	1,348
483+40 TO 515+74	Inside Shld.			1,439	1,439
517+42 TO 576+58	Inside Shld.			2,630	2,630
577+92 TO 605+85	Inside Shld.			1,248	1,248
607+39 TO 678+00	Inside Shld.			3,143	3,143
STAGE 2					
U.S. 45					
449+88 TO 449+88		75,035	83,725	75,035	
449+88 TO 482+39	Outside Shld.			3,172	3,172
482+81 TO 516+39	Outside Shld.			3,731	3,731
516+68 TO 576+03	Outside Shld.			6,668	6,668
577+11 TO 606+31	Outside Shld.			3,201	3,201
606+49 TO 694+55	Outside Shld.			9,740	9,740
694+83 TO 710+81	Outside Shld.			1,738	1,738
449+88 TO 482+09	Inside Shld.			1,433	1,433
482+81 TO 515+78	Inside Shld.			1,492	1,492
516+63 TO 576+81	Inside Shld.			2,663	2,663
577+43 TO 605+89	Inside Shld.			1,300	1,300
606+81 TO 693+05	Inside Shld.			3,678	3,678
693+19 TO 705+20	Inside Shld.			468	468
STAGE 3					
U.S. 45					
678+00 TO 706+32		9,082	10,027	9,082	
689+34 TO 693+69		440	385	440	
678+00 TO 694+48	Outside Shld.			1,819	1,819
694+71 TO 706+32	Outside Shld.			1,255	1,255
678+00 TO 694+18	Inside Shld.			748	748
686+15 TO 706+32	Inside Shld.			484	484
689+05 TO 693+69	Inside Shld.			208	208
PROJECT TOTAL		150,668	167,402	228,323	76,225

**RECESSED PAVEMENT MARKING
GROOVING ALT. BID B**

STATION BEGIN	STATION END	*SIDE	LOCATION	DESCRIPTION	GROOVING FOR RECESSED PAVEMENT MARKING	
					5" WHITE FOOT	YELLOW FOOT
STAGE 3						
U.S. 45						
449+88	705+27	LT CL	SB	SKIP DASH	0,385	
449+88	703+47	RT CL	NB	SKIP DASH	0,340	
707+82	710+61	CL	SB	SKIP DASH		70
PROJECT TOTAL					12,725	70

* IS = INSIDE LANE, OS = OUTSIDE LANE, LT & RT ARE BASED ON FORWARD STATIONING

△ REVISED 7-22-14

NOTE:
LIMITS SHOWN FOR PAY ITEMS
ON THESE SCHEDULES MAY HAVE
ADDITIONAL LIMITS AND VALUES
IN OTHER SCHEDULES.

FILE NAME *	USER NAME * bsnery	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES ALTERNATE BID B			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PROJECT NAME * 2011 Projects\11277 - 1001 US	PROJECT NUMBER * 11277-1001	DRAWN -	REVISED -					332	(29,30)R-1	SALINE	745	66
PLOT SCALE * 100.00' / in.	PLOT DATE * 7/21/2014	CHECKED -	REVISED -		SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 78077		
		DATE	REVISED -									