

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				RURAL		RURAL	
				SALINE 80% FED. 20% STATE	SALINE 80% FED. 20% STATE	SALINE 80% FED. 20% STATE	SALINE 80% FED. 20% STATE
				ROADWAY 0003 URBAN	ROADWAY 0003 RURAL	BRIDGE 0014 S.N. 083-6008	BOX CULVERT 0040 S.N. 083-2023
30201500	LIME	TON	8,941.2	770.3	8,170.9		
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1,818	1,818			
35100100	AGGREGATE BASE COURSE, TYPE A	TON	645	362	283		
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	1,996	1,996			
35100800	AGGREGATE BASE COURSE, TYPE A 9"	SQ YD	23,167		23,167		
40200200	AGGREGATE SURFACE COURSE, TYPE A	CU YD	375	109	266		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1,670		1,670		
<del>40300300</del>	<del>BITUMINOUS MATERIALS (COVER AND SEAL COATS)</del>	<del>GALLON</del>	<del>1,985</del>		<del>1,985</del>		
<del>40300500</del>	<del>COVER COAT AGGREGATE</del>	<del>TON</del>	<del>33</del>		<del>33</del>		
<del>40300600</del>	<del>SEAL COAT AGGREGATE</del>	<del>TON</del>	<del>17</del>		<del>17</del>		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	207	207			
40600990	TEMPORARY RAMP	SQ YD	69	69			
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1,868	56	1,812		
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	2,768	117	2,651	43	

\* SPECIALTY ITEM

FILE NAME :	USER NAME : bemaey	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
P:\Projects\2011 Projects\11297 - 100T US95 Ph2\CV\CADD Sheets\0978077-shs-500.dgn	DRAWN -	REVISED -	332					(29,30R-1)	SALINE	745	8	
PLOT SCALE : 100.00' / in.	CHECKED -	REVISED -	CONTRACT NO. 78077					ILLINOIS FED. AID PROJECT				
PLOT DATE : 1/28/2014	DATE -	REVISED -	SCALE: N.T.S.					3	STA.	TO STA.		