

LOT SCALE = 100.000 '/ in.

PLOT DATE = 4/30/2014

CHECKED

DATE

REVISED

REVISED

PERIMETER EROSION BARRIER

(SILT FILTER FENCE) PROPOSED BARRIER

ISOMETRIC VIEW

OF INSTALLATION

THIS WORK SHALL COMPLY WITH ALL THE REQUIREMENTS OF THE STANDARD SPECIFICATION SECTION 280 FOR TEMPORARY EROSION AND SEDIMENT CONTROL, EXCEPT AS MODIFIED IN THESE

THE BARRIER FABRIC SHALL MEET THE REQUIREMENTS OF ART. 208.02 AND 1080.02 FOR SILT FILTER FENCE AND ARTICLE 280.04(b) FOR PERIMETER EROSION BARRIER.

THE POSTS SHALL BE PLACED AS SHOWN ON HIGHWAY STANDARD 280001.

THIS WORK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER FOOT FOR PERIMETER EROSION BARRIER, AS MEASURED IN PLACE. THE UNIT PRICE SHALL INCLUDE THE COST OF ALL MATERIAL. EQUIPMENT AND LABOR TO CONSTRUCT THE FENCE AS DESCRIBED.

> REVISIONS REDRAWN 2-15-89 REVISED 8-18-94 REVISED 10-3-9 REVISED 12-17-01 RESIZED 5-7-08

STD. 9-40

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

COUNTY TOTAL SHEET NO. SALINE 745 488 SECTION **DETAILS** (29,30)R-1 332 CONTRACT NO. 78077 SCALE: SHEET NO. OF SHEETS STA. TO STA. FED. ROAD DIST. NO. | ILLINOIS FED. AID PROJECT