

lkr\d0181440\7819	6-shts.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS	SIGNS - RUUGH GRUUV				
	PLOT SCALE = 200.0000 ' / in.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	UNEVEN LANE				
	PLOT DATE = 6/5/2014	DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	

<u>UNEVEN</u> LANES SIGN W8-11 (48'' × 48'')

COLORS:

LEGEND AND BORDER - BLACK NON-REFLECTORIZED BACKGROUND - ORANGE REFLECTORIZED

NOTE: PRIOR TO ALLOWING TRAFFIC ON ANY PORTION OF THE ROADWAY THAT HAS BEEN COLDMILLED OR BEFORE RESURFACING OPERATIONS BEGIN, THE CONTRACTOR SHALL HAVE ERECTED "UNEVEN PAVEMENT" SIGNS THAT CONFORM TO THE ABOVE DETAILS. A MINIMUM OF ONE SIGN AT EACH END OF THE IMPROVEMENT WILL BE REQUIRED. THE CONTRACTOR SHALL MAINTAIN THE "UNEVEN PAVEMENT" SIGNS UNTIL THE RESURFACING OPERATIONS ARE COMPLETED.

> IF AT ANY TIME THE SIGNS ARE IN PLACE BUT NOT APPLICABLE, THEY SHALL BE TURNED FROM THE VIEW OF MOTORISTS OR COVERED AS DIRECTED BY THE ENGINEER.

THE COST OF FURNISHING, ERECTING, MAINTAINING, AND REMOVING THE REQUIRED SIGNS SHALL BE INCLUDED IN THE CONTRACT. REVISIONS

				STD.	DRAWN REVISE REDSIG RESIZE 9-41 REVIEV	D 4-0 NED 7-2 D 5-0	6-93 3-04 8-08	
OVED SURFACE,		F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ANES		780	(6,6-1)RS-2	HARDIN	15	15		
ANLO		CONTRACT NO.			T NO.	78196		
5	STA.	TO STA.	ILLINOIS FED. AID PROJECT					