

# SUMMARY OF QUANTITIES

LOCATION:	URBAN	RURAL
COUNTY:	FRANKLIN	
ROUTE:	IL 149	I-57
FUNDING:	100% STATE	100% STATE
	ROADWAY 0005	ROADWAY 0004

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0005	ROADWAY 0004
20200100	EARTH EXCAVATION	CU YD	92.0	0.0	92.0
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	273.0	0.5	272.5
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	92.0	0.3	91.7
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1196.0	0.0	1196.0
42001200	PAVEMENT FABRIC	SQ YD	49.0	49.0	0.0
44000100	PAVEMENT REMOVAL	SQ YD	1196.0	0.0	1196.0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	115.0	0.0	115.0
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	411.0	411.0	0.0
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	22.0	22.0	0.0
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	27.0	27.0	0.0
44201299	DOWEL BARS 1 1/2"	EACH	1040.0	1040.0	0.0
44213200	SAW CUTS	FOOT	2844.0	2844.0	0.0
44213204	TIE BARS 3/4"	EACH	692.0	20.0	672.0