

LAYOUT	BAB	6/12/2020
DRAWN	RLA	6/13/19
REVIEWED	MGD	7/10/2024

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE - 0004 ROADWAY	CONSTRUCTION CODE - 0021 SIGNAL	CONSTRUCTION CODE - 0043 WATER MAIN	CONSTRUCTION CODE - 0043 WATER MAIN (RELOCATION)	CONSTRUCTION CODE - 0043 SANITARY SEWER (RELOCATION)
70307210	TEMPORARY PAVEMENT MARKING - LINE 24"- TYPE IV TAPE	FOOT	26	26				
72000100	SIGN PANEL - TYPE 1	SQ FT	133	103	30			
72000200	SIGN PANEL - TYPE 2	SQ FT	70		70			
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	231	231				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	680	680				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	15,875	15,875				
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	829	829				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	699	699				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	247	247				
78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63	63				
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	810	810				
78300201	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	572	572				
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	20	20				
80500100	SERVICE INSTALLATION, TYPE A	EACH	1		1			

FILE NAME =	USER NAME = Becks01673	DESIGNED - BAB	REVISED - 07/22/2025
It:\15\Jobs\15L0098C\CAD\Road\Sheet\Plan\Set 2\sh-t-S000001.dgn		DRAWN - RLA	REVISED -
		CHECKED - MGD	REVISED -
S00 11		DATE - 11/21/2024	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HAMILTON ROAD
SUMMARY OF QUANTITIES

SCALE: N/A SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	24-00360-01-PV	McLEAN	192	14
CONTRACT NO.91653				
ILLINOIS FED. AID PROJECT				

THERMOPLASTIC PAVEMENT MARKING SCHEDULE						
LOCATION		78000100	78000400	78000500	78000600	78000650
		THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"
BEGIN STATION	END STATION	SQ FT	FOOT	FOOT	FOOT	FOOT
HAMILTON ROAD						
9+90.18	15+00.00	31	1,714	184	57	
15+00.00	21+00.00	140	1,968	325	201	127
21+00.00	27+00.00	62	1,801			
27+00.00	32+50.00	78	1,767	50	140	20
32+50.00	38+50.00	94	1,732	76		
38+50.00	42+76.00	213	673			100
BUNN STREET						
202+21.27	206+00.00	31	1,727	103	158	
208+00.00	211+51.93	31	1,673	91	143	
RHODES LANE						
302+00.00	313+00.00		2,200			
313+00.00	316+26.21		620			
TOTAL		680	15,875	829	699	247

RIPRAP SCHEDULE					
LOCATION		25100900	28100105	28100107	28200200
		TURF REINFORCEMENT MAT	STONE RIPRAP, CLASS A3	STONE RIPRAP, CLASS A4	FILTER FABRIC
BEGIN STATION	END STATION	SQ YD	SQ YD	SQ YD	SQ YD
HAMILTON ROAD					
9+90.18	15+00.00				
15+00.00	21+00.00				
21+00.00	27+00.00				
27+00.00	32+50.00			118	118
32+50.00	38+50.00				
38+50.00	44+00.00	90			
BUNN STREET					
202+21.27	206+00.00				
208+00.00	211+51.93				
RHODES LANE					
302+00.00	307+00.00				
307+00.00	308+60.21				
314+00.00	317+50.00		8	31	31
317+50.00	322+00.00				
322+00.00	326+44.09				
TOTAL		90	8	149	149

FENCE SCHEDULE		
LOCATON		66500105
		WOVEN WIRE FENCE, 4'
BEGIN STATION	END STATION	FOOT
HAMILTON ROAD		
9+90.18	15+00.00	
15+00.00	21+00.00	
21+00.00	27+00.00	
27+00.00	32+50.00	
32+50.00	38+50.00	
38+50.00	42+76.00	
BUNN STREET		
202+21.27	206+00.00	
208+00.00	211+51.93	289
RHODES LANE		
301+00.00	306+00.00	
306+00.00	308+60.21	
314+54.05	318+00.00	
TOTAL		289

SIGN SCHEDULE					
LOCATION			72000100	72000200	72800100
			SIGN PANEL - TYPE 1	SIGN PANEL - TYPE 2	TELESCOPING STEEL SIGN SUPPORT
STATION	OFFSET	SIGN	SQ FT	SQ FT	FOOT
HAMILTON ROAD					
18+00.00	39.50' RT	R2-1	5.00		15.50
29+75.00	40.50' RT	W11-2	9.00		17.50
		W16-9P	2.00		
30+86.00	40.50' RT	W16-7P	2.00		18.50
		W11-2	9.00		
31+12.00	28.50' LT	W16-7P	2.00		18.50
		W11-2	9.00		
32+25.00	28.50' LT	W11-2	9.00		17.50
		W16-9P	2.00		
39+18.95	40.00' RT	W10-1	7.10		16.00
40+05.00	27.00' LT	W10-1	3.10		15.00
RHODES LANE					
300+58.50	25.82' LT	W4-4	2.00		20.25
		R1-1	6.25		
		Street Sign-1	1.88		
		Street Sign-1	1.88		
		Street Sign-2	1.50		
		Street Sign-2	1.50		
301+50.00	19.00' RT	W14-2	6.25		16.50
317+25.00		R11+100	7.50		15.50
317+25.00	5.00' LT	OM 4-1	2.25		14.50
317+25.00	5.00' RT	OM 4-1	2.25		14.50
BUNN STREET					
205+42.00	26.50' LT	R2-1	5.00		15.50
208+60.00	21.75' RT	R2-1	5.00		15.50
FROM SIGNAL PLANS			30.00	69.75	
TOTAL			132.46	69.75	230.75
TOTAL (ROUNDED)			133.00	70.00	231.00
ALL STREET SIGNS SHALL HAVE 6" SERIES B LETTERS.					



MODIFIED URETHANE PAVEMENT MARKING SCHEDULE			
LOCATION		78009000	78009004
		MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"
BEGIN STATION	END STATION	SQ FT	FOOT
MORRISSEY DRIVE			
496+00.00	499+27.81	63	810
TOTAL		63	810

LAYOUT	BAB	6/12/2020
DRAWN	RLA	6/13/19
REVIEWED	MGD	7/10/2024

FILE NAME =	USER NAME = Becks01673	DESIGNED - BAB	REVISED - 07/22/2025
It:\15\Jobs\15L0098C\CAD\Road\Sheet\Plan\Set 2\sh-t-schedule04.dgn		DRAWN - RLA	REVISED -
	PLOT SCALE = 2.0000 ' / in.	CHECKED - MGD	REVISED -
Default	PLOT DATE = 7/21/2025	DATE - 11/21/2024	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HAMILTON ROAD
SCHEDULE OF QUANTITIES

SCALE: N/A SHEET OF SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6371	24-00360-01-PV	McLEAN	192	30
CONTRACT NO.91653				
ILLINOIS FED. AID PROJECT				