SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	39
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42
20100500	TREE REMOVAL, ACRES	ACRE	1.12
20300100	CHANNEL EXCAVATION	CU YD	1091
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	471
25000312	SEEDING, CLASS 4A	ACRE	0.18
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	16
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	16
25100125	MULCH, METHOD 3	ACRE	0.18
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	3,152
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	161
28000300	TEMPORARY DITCH CHECKS	FOOT	75
28000400	PERIMETER EROSION BARRIER	FOOT	523
28000500	INLET AND PIPE PROTECTION	EACH	2
28000510	INLET FILTERS	EACH	11
28100107	STONE RIPRAP, CLASS A4	SQ YD	823
28200200	FILTER FABRIC	SQ YD	823
35102100	AGGREGATE BASE COURSE, TYPE B, 9"	SQ YD	1,935
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	155
40600300	AGGREGATE (PRIME COAT)	TON	4
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	168
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	197
44000100	PAVEMENT REMOVAL	SQ YD	1,935
44000161	HOT-MIX ASPHALT SURFACE REMOVAL 3"	SQ YD	400
*44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,225
50105220	PIPE CULVERT REMOVAL	FOOT	259
50200100	STRUCTURE EXCAVATION	CU YD	211
50300225	CONCRETE STRUCTURES	CU YD	47.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10,670
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	2
54002020	EXPANSION BOLTS $\frac{3}{4}$ INCH	EACH	14
54010903	PRECAST CONCRETE BOX CULVERT 9' X 3'	FOOT	143
54010704	PRECAST CONCRETE BOX CULVERT 7' X 4'	FOOT	131
54020702	PRECAST CONCRETE BOX CULVERT 7' X 2'	FOOT	1,084
54020804	PRECAST CONCRETE BOX CULVERT 8' X 4'	FOOT	588
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
550A0330	STORM SEWERS, CLASS A, TYPE 2 10"	FOOT	10

* INDICATES NON-STANDARD ITEM COVERED BY SPECIAL PROVISION

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	20
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	15
*66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	663
*67000500	ENGINEERS FIELD OFFICE, TYPE B	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	385
*	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
*	WOOD INFORMATION SIGNS	EACH	2
*	CONSTRUCTION STAKING	L SUM	1
*	TEMPORARY COFFERDAM SYSTEM	L SUM	1
*	SEEDING, MULCHING, AND FERTILIZING	ACRE	0.78
*	SEEDING AND FERTILIZING	ACRE	0.65

Designed By TMM Checked By RJM
Drawn By RJM Checked By TMM
7/8/2013 10:04:53 AM O:\OwrProj\Impl\Projects\Crystal Creek IIB\Plan Sheets\3 Summary of Quantities.dgn