

F.A.P. RT.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	130N-3 (1)	DUPAGE	141	11
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60R46

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	100% WEST CHICAGO FIRE PROTECTION	80% FED, 10% STATE 5% W CHICAGO, 5% DUPAGE CO		80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
				ROADWAY	TRAFFIC SIGNALS			INTERCONNECT		LIGHTING
				0003	0021			0021		0021
				URBAN	POWIS ROAD	POWIS ROAD	PHEASANT RUN	NORTH AVE	URBAN	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1444			1444				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4090			4090				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	73			73				
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1 C	FOOT	927			927				
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	2			2				
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1			1				
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1			1				
87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1			1				
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1			1				
87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1			1				
87703060	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 65 FT.	EACH	1			1				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20			20				
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	50			50				

* DENOTES SPECIALTY ITEM

AECOM

S00-08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 307 (ILLINOIS ROUTE 64)

SUMMARY OF QUANTITIES

SCALE: VERT: NONE
 HORIZ: NONE
 DATE: FEBRUARY 1, 2013

DRAWN BY: AFC
 CHECKED BY: NJH