

80% FED. / 20% STATE

CONSTRUCTION CODE

URBAN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 0004 URBAN	BRIDGE 0014 S.N. 049-0087
44000100	PAVEMENT REMOVAL	SQ YD	479	479	
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	1016	1016	
44000400	GUTTER REMOVAL	FOOT	571	571	
44004000	PAVED DITCH REMOVAL	FOOT	238	238	
44201298	DOWEL BARS 1 1/4"	EACH	16	16	
44213204	TIE BARS 3/4"	EACH	307	307	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1118	1118	
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	289	289	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	746	746	
50102400	CONCRETE REMOVAL	CU YD	15.9		15.9
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4	
50104650	SLOPE WALL REMOVAL	SQ YD	51		51
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1
50157300	PROTECTIVE SHIELD	SQ YD	361		361

* - DENOTES SPECIALTY ITEM

FILE NAME * 1:\6710\6710.24 - IL 43 0-4- US 41\CADD\ADD Sheets\DI6061-shr-500.dgn	USER NAME * rgo11	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS
		STA.	TO STA.

P.A. RTE. 2706	SECTION 125 HB-BR	COUNTY LAKE	TOTAL SHEETS 51	SHEET NO. 5
CONTRACT NO. 6061				
ILLINOIS FED. AID PROJECT				