

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	ALIGNMENT AND BENCHMARKS
5	EROSION CONTROL AND RESTORATION PLAN
6	DRAINAGE PLAN AND PROFILE
7-12	S. U. E. PLANS
13	DRIVEWAY DETAILS - DISTANCE BETWEEN R. O. W. AND FACE OF CURB IS LESS THAN 15' (B002)
14	DETAILS FOR DEPRESSED CURB & GUTTER AND SHOULDER TREATMENT AT TBT TY 1 SPL (BD 34)
15	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC 10)
16	ARTERIAL ROAD INFORMATION SIGN (TC 22)

HIGHWAY STANDARDS

STD. NO.	TITLE
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
280001-07	TEMPORARY EROSION CONTROL SYSTEMS
424026-01	ENTRANCE / ALLEY PEDESTRIAN CROSSINGS
542001-03	CONCRETE END SECTIONS FOR PIPE CULVERTS 15" THRU 84" DIAMETER
602401-03	MANHOLE, TYPE A
602601-02	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701-02	MANHOLE STEPS
604001-03	FRAME AND LIDS, TYPE 1
701101-03	OFF ROAD OPERATIONS, MULTILANE, 15' TO 24' FROM PAVEMENT EDGE
701106-02	OFF ROAD OPERATIONS, MULTILANE, MORE THAN 15' (4.5 m) AWAY
701601-08	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701901-02	TRAFFIC CONTROL DEVICES

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "J. U. L. I. E." AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED).
- THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM 72 HOURS IN ADVANCE OF BEGINNING WORK.
- THE CONTRACTOR SHALL BE REQUIRED TO PROVIDE ACCESS TO ABUTTING PROPERTY AT ALL TIMES DURING THE CONSTRUCTION OF THIS PROJECT.
- IT SHALL BE THE CONTACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- FOR STORM SEWER CONSTRUCTED UNDER THE ROADWAY, BACKFILLING METHODS TWO AND THREE AUTHORIZED UNDER THE PROVISIONS OF ARTICLE 550.07 OF THE STANDARD SPECIFICATIONS WILL NOT BE ALLOWED.
- THE COST OF CONNECTING EXISTING STORM SEWERS TO PROPOSED STORM SEWERS AND TO PROPOSED DRAINAGE STRUCTURES AND THE COST OF CONNECTING PROPOSED STORM SEWERS TO EXISTING DRAINAGE STRUCTURES WILL NOT BE PAID FOR SEPARATELY BUT INCLUDED IN THE COST OF THE VARIOUS DRAINAGE ITEMS.

FILE NAME *	USER NAME * I485	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ASHLAND AVE. (THORNTON RD. - BROADWAY ST.) INDEX OF SHEETS, HIGHWAY STANDARDS, AND GENERAL NOTES				F.A.U. RTG.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
H:\Jobs\2011\20113012-06\CAD\Site\dgn\00	60R82\0160R82-idx-gennote.dgn	DRAWN - EF	REVISED -		2857	146-T	COOK	16	2				
	PLOT SCALE * 1/8" = 1' in.	CHECKED - RS	REVISED -		CONTRACT NO. 60R82				ILLINOIS FED. AID PROJECT				
	PLOT DATE * 4/25/2013	DATE - 05-09-2013	REVISED -		SCALE: 1"=50'	SHEET 1 OF 1	SHEETS STA.	TO STA.					