

URBAN

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	TRAFFIC SIGNALS 0021							
				ROADWAY 0003			US 30 WB RAMPS (A&B) @ WATKINS/IL RT 31		CASE ST @ IL RT 31 (TEMP SIGNAL)	US 30 AT IL 31 RAMPS (TEMP SIGNAL)	INTERCONNECT
				KANE COUNTY	KANE COUNTY	VILLAGE OF MONTGOMERY	KANE COUNTY	KANE COUNTY	KANE COUNTY		
				80% FED 20% STATE	80% FED 20% STATE	100% VILLAGE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE		
48203047	HOT-MIX ASPHALT SHOULDERS, 12 1/2"	SO YD	106	106							
48203048	HOT-MIX ASPHALT SHOULDERS, 12 3/4"	SO YD	361	361							
50300300	PROTECTIVE COAT	SO YD	627	627							
54261424	CONCRETE END SECTION, STANDARD 542001, 24", 1:4	EACH	2	2							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	10	10							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	334	334							
55100900	STORM SEWER REMOVAL 18"	FOOT	88	88							
55101200	STORM SEWER REMOVAL 24"	FOOT	10	10							
56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1							
60107600	PIPE UNDERDRAINS 4"	FOOT	129	129							
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	76	76							
60200805	CATCH BASINS, TYPE A, 4' -DIAMETER, TYPE B GRATE	EACH	1	1							
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4							
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1							
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1							
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1							
60500050	REMOVING CATCH BASINS	EACH	1	1							
60600605	CONCRETE CURB, TYPE B	FOOT	97	97							
60603800	COMBINATION CONCRETE CURB AND CUTTER, TYPE B-6.12	FOOT	796	796							

h:\jobs\2010\20103003\code\site\sgn\01060453-sht-Sum01ys.dgn
 5/16/2013 2:44:45 PM

USER NAME * 1854	DESIGNED - JWB	REVISED -
	DRAWN - JWB	REVISED -
PLOT SCALE * 100.0000' / 1"	CHECKED - RS	REVISED -
PLOT DATE * 5/16/2013	DATE - 05/17/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WATKINS STREET AT IL ROUTE 31
SUMMARY OF QUANTITIES

SHEET S00-3 OF 8

F.A.U. R.T.E. 3902	SECTION 12R-N	COUNTY KANE	TOTAL SHEETS 92	SHEET NO. 6
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60V53	