

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2013-001-I	COOK	10	5A.

CONTRACT: 60W18

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
6044 South Moody Avenue	10.0	1.7	1.4	9.0	0.0	0.0	0.0	0.0	0.0	Replace 10 ft of crumbling curb and carriage walk.
6201 South Moody Avenue	0.0	0.0	0.0	0.0	120.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares in front and 2 sidewalk squares on the side of the house.
5514 South Mulligan Avenue	0.0	0.0	0.0	0.0	0.0	0.0	350.0	0.0	15.0	Replace 15 ft of curb and Alley Apron
5815 South Nagle Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares
5816 South Narragansett Avenue	15.0	2.5	2.0	4.5	0.0	0.0	0.0	0.0	0.0	Replace 15 feet of damaged curb and gutter
5926 South Narragansett Avenue	30.0	5.0	4.4	6.0	0.0	0.0	0.0	0.0	0.0	Replace 30 feet of damaged curb and gutter
6348 South Narragansett Avenue	15.0	2.5	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace curb and alley apron
5800 South Nashville Avenue	0.0	0.0	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace Alley Apron
6206 South Nashville Avenue	10.0	1.7	1.7	0.0	0.0	0.0	0.0	0.0	0.0	Replace 10 ft of curb and gutter.
5817 South Natchez Avenue	0.0	0.0	0.0	12.0	210.0	0.0	0.0	0.0	0.0	Replace 7 Sidewalk Squares
5924 South Natoma Avenue	30.0	5.0	0.0	45.0	0.0	0.0	0.0	0.0	0.0	Replace curb and courtesy walk (new curb to be painted).
5958 South Natoma Avenue	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares.
6009 South Natoma Avenue	20.0	3.4	0.0	30.0	0.0	0.0	0.0	0.0	0.0	Replace broken curb
5606 South Neenah Avenue	0.0	0.0	0.0	13.5	30.0	0.0	0.0	0.0	0.0	Replace 1 Sidewalk Square and 3 Courtesy Walk Squares.
5858 South New Castle Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 6 sidewalk squares on 59th Street side of house causing tripping hazard.
5758 South New England Avenue/ 5759 South New England Ave.	20.0	3.4	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace Alley apron with concrete.
5720 South Normandy Avenue	0.0	0.0	0.0	40.5	240.0	0.0	0.0	0.0	0.0	Replace 8 Sidewalk Squares, Courtesy Walk, and Carriage Walk
5751 through 5755 South Normandy Avenue	50.0	8.4	2.0	57.0	0.0	0.0	0.0	0.0	0.0	Replace 50 ft of curb and gutter (standing water).
5808 South Normandy Avenue	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 5.5 Sidewalk Squares
5914 South Normandy Avenue	20.0	3.4	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace Alley Apron
5915 South Normandy Avenue	20.0	3.4	0.0	0.0	60.0	0.0	350.0	0.0	30.0	Replace 2 Sidewalk Squares and Alley Apron.
5917 South Normandy Avenue	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares
5920 South Normandy Avenue	0.0	0.0	0.0	9.0	0.0	0.0	0.0	0.0	0.0	Replace courtesy walk
SUB-TOTAL	240.0	40.4	11.5	226.5	1260.0	0.0	2100.0	0.0	165.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES