

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2013-001-I	COOK	10	50.

CONTRACT: 60W18

LOCATION	COMB. CONC. C & G R&R (LF)	HMA SURF R&R VARIABLE DEPTH (SQYD)	SALT TOLERANT SODDING (SQYD)	SIDEWALK 5" R&R (SQFT) 18" CARRIAGE/ COURTESY	SIDEWALK 5" R&R (SQFT) 5' PARALLEL	SIDEWALK 8" R&R (SQFT) 5' PARALLEL	DRIVEWAY 8" R&R (SQFT)	DETECTABLE WARNINGS (ADA RAMPS) (SQFT)	CONC. CURB, TYPE B (LF)	REMARKS
6703 West 59th Street	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares
6707 West 59th Street	0.0	0.0	0.0	9.0	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares and 2 Carriage Walk Squares
6709 West 59th Street	0.0	0.0	0.0	22.5	0.0	0.0	0.0	0.0	0.0	Replace Courtesy Walk and Carriage Walk
6735 West 59th Street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares on Rutherford Avenue Side of House Adjacent to Tree
6540 West 60th Street	2.0	0.4	0.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 2 feet of damaged curb
5900 West 63rd Place	0.0	0.0	0.0	0.0	0.0	0.0	350.0	0.0	30.0	Replace Curb and Alley Apron
6031 West 63rd Place	0.0	0.0	0.0	31.5	60.0	0.0	0.0	0.0	0.0	Replace 2 Sidewalk Squares Near East Side of Property and Courtesy Walk. *PLEASE CONFIRM SIDEWALK SQUARES WITH HOMEOWNER FIRST*
4322 West 63rd Street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares
5857-5859 West 63rd Street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 Sidewalk Squares
3923 West 64th Place	0.0	0.0	0.0	0.0	180.0	0.0	0.0	0.0	0.0	Replace 5 sidewalk squares (tripping hazard).
5800 West 64th Place	30.0	5.0	5.0	0.0	0.0	0.0	0.0	0.0	0.0	On Menard Avenue side, replace 30 ft of crumbling curb
3900 West 64th Street	7.0	1.2	1.2	0.0	0.0	0.0	0.0	0.0	0.0	Repair 7 feet of daamaged curb (side of home) closest to alley
5914 West 64th Street	2.0	0.4	0.0	3.0	0.0	0.0	0.0	0.0	0.0	Replace 2 feet of damaged curb
6015 West 64th Street	20.0	3.4	3.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 20 ft of missing and damaged curb.
6158 West 64th Street	0.0	0.0	0.0	0.0	0.0	0.0	30.0	12.0	6.0	Make Alley Handicap/ADA Accessible
4525 West 65th Place	0.0	0.0	0.0	0.0	210.0	0.0	0.0	0.0	0.0	Replace 7 sidewalk squares
4528 West 65th Place	12.0	2.0	0.0	0.0	0.0	0.0	18.0	0.0	0.0	Replace cracked, broken curb and gutter causing standing water issue (entrance of the driveway)
3825 West 66th Street	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 Sidewalk Squares
3911 West 66th Street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 Sidewalk Squares
3631 West 67th Place	0.0	0.0	0.0	0.0	60.0	0.0	0.0	0.0	0.0	Replace 2 sidewalk squares (standing water).
3655 West 68th Street	0.0	0.0	0.0	0.0	90.0	0.0	0.0	0.0	0.0	Replace 3 sidewalk squares
3811 West 68th Street	0.0	0.0	0.0	46.5	0.0	0.0	0.0	0.0	0.0	Replace 31 Feet of Cracked, Sunken Catwalk adjacent to curb
3820 West 68th Street	1.5	0.3	0.3	0.0	0.0	0.0	0.0	0.0	0.0	Replace 1.5 Feet of Crumbling Curb
3829 West 68th Street	1.5	0.3	0.3	13.5	0.0	0.0	0.0	0.0	0.0	Replace 1.5 Feet of Crumbling Curb & 9 Feet of Cracked Sinking Catwalk Along
3830 West 68th Street	2.0	0.4	0.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Crumbling Curb
3835 West 68th Street	2.0	0.4	0.4	43.5	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Cracked, Crumbling Curb & 29 Feet of Sunken, Cracked Catwalk adjacent to curb
3839 West 68th Street	0.0	0.0	0.0	85.5	0.0	0.0	0.0	0.0	0.0	Replace 27 Feet of Cracked, Buckling Catwalk Adjacent to Curb, as well as 3' x 10' service walk, ADA Handicap Accessible
3841 West 68th Street	0.0	0.0	0.0	40.5	0.0	0.0	0.0	0.0	0.0	Replace 27 Feet of Sunken Catwalk Adjacent to Curb
3849 West 68th Street	2.0	0.4	0.0	3.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Cracked, Crumbling Curb
3854-3858 West 68th Street	10.0	1.7	1.7	0.0	0.0	0.0	0.0	0.0	0.0	Repair 10 ft of curb
3859 West 68th Street	2.0	0.4	0.4	0.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Feet of Crumbling Curb
3735 West 69th Street	0.0	0.0	0.0	0.0	360.0	0.0	0.0	0.0	0.0	Replace 12 sidewalk squares
3828 West 69th Place	0.0	0.0	0.0	0.0	240.0	0.0	0.0	0.0	0.0	Replace 8 sidewalk squares
3916 West 70th Place	0.0	0.0	0.0	0.0	150.0	0.0	0.0	0.0	0.0	Replace 5 cracked sidewalk squares
3917 West 70th Place	0.0	0.0	0.0	45.0	0.0	0.0	0.0	0.0	0.0	Replace 2 Sinking Courtesy Walk Squares and 8 Carriage Walk Squares
SUB-TOTAL	94.0	16.3	13.5	343.5	2100.0	0.0	398.0	12.0	36.0	
TOTAL	628.0	106.2	46.5	1104.0	10920.0	0.0	3898.0	292.0	341.0	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES