CODE NO.	ITEM	UNIT	90% FED. 10% STATE URBAN TOTAL QUANTITY	CONSTRUCTION CODE ROADWAY 0004 URBAN	BRIDGE 0011 016-1709	RETAINING WALL 0040 016-1724		LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	UTILITY 0043 URBAN
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	3	3						
58700300	CONCRETE SEALER	SQ FT	8728		8728 △1					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	448 △1		391	57 △1				
~~59300100~~	~~CONTROLLED LOW STRENGTH MATERIAL~~	~~CU YD~~	~~845~~							
60107700	PIPE UNDERDRAINS 6"	FOOT	134	134 △1						
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	17	17						
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1						
60201310	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 20 FRAME AND GRATE	EACH	4	4						
60201340	CATCH BASINS, TYPE A 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3						
~~60208210~~	~~CATCH BASINS, TYPE C, TYPE 20 FRAME AND GRATE~~	~~EACH~~	~~3~~	~~3~~						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
~~60234200~~	~~INLETS, TYPE A, TYPE 1 FRAME, OPEN LID~~	~~EACH~~	~~1~~	~~1~~						
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	2	2						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	7	7						
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2						

* DENOTES SPECIALTY ITEM ** DENOTES NON-PARTICIPATING ITEM

△1 Rev. 7-19-13 Rev.

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

D160W25-sht-SQD	DESIGNED - JWM	REVISED -	
USER NAME = pimsarno	DRAWN - JWM	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - AC	REVISED -	
PLOT DATE = 5/16/2013	DATE - 5/14/2013	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 6 OF 21 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	10

CONTRACT NO. 60W25
ILLINOIS FED. AID PROJECT

FILE PATH = pw:\\388039-pwint\aecomonline.local:PWAECOM00\Documents\01 Americas\Transportation\60269938 Circle\Phase II\000 CAD\006 Roadway\Sheets\60W25 Contract\D160W25-sht-SQD