

90% FED.
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE						
				ROADWAY 0004 URBAN	BRIDGE 0011 016-1709	RETAINING WALL 0040 016-1724	LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	UTILITY 0043 URBAN	
88600100	DETECTOR LOOP, TYPE I	FOOT	183						183	
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1						1	
* 89502380	REMOVE EXISTING HANDHOLE	EACH	4						4	
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6						6	
X0321903	MICRO-PILES	EACH	4							4
* X0322141	REMOVE TEMPORARY WOOD POLE	EACH	1						1	
X0322400	PILE EXTRACTION	EACH	27			27				
* X0322689	POLE, STEEL, ANCHOR BASE, 10" DIA., 7-GAUGE, 34' -6"	EACH	1						1	
X0323044	COARSE SAND PLACEMENT	SQ YD	426	426						
X0324198	REMOVAL OF ASBESTOS CEMENT CONDUIT	FOOT	1280						1280	
X0324345	COMBINED SEWER REMOVAL 24"	FOOT	34	34						
X0324465	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	1358							1358
* X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1						1	
X0325207	TELEVISION INSPECTION OF SEWER	FOOT	4191	4191						
* X0326148	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 15 FT. MAST ARM	EACH	3						3	

* DENOTES SPECIALTY ITEM

** DENOTES NON-PARTICIPATING ITEM

Rev. 7-19-13

Rev.

FILE PATH: ... \388231-print\loc\online\isell\paw\CD\03\Documents\01_America\Transportation\6626938_Cricle\Phase 1\1800_60W25_Roadway\Sheet\6626938_Contract\016626938.dwg



016626938-60W25
USER NAME = pmarno
PLOT SCALE = 1,0000' / 1" =
PLOT DATE = 5/16/2013

DESIGNED - JWM
DRAWN - JWM
CHECKED - AC
DATE - 5/14/2013

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 14 OF 21 SHEETS STA. TO STA.

F.A.L. RTE. 90/94/290	SECTION 2013-00TR	COUNTY COOK	TOTAL SHEETS 317	SHEET NO. 18
CONTRACT NO. 60W25				
ILLINOIS FED. AID PROJECT				