90% FED.
10% STATE

	CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE: ROADWAY 0004 URBAN	BRIDGE 0011 016-1709	RETAINING WALL 0040 016-1724		LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN	UTILITY 0043 URBAN
*	X0326326	CABLE IN CONDUIT, TRIPLEX, 2-1/C NO. 6 AND 1-1/C NO. 8 GROUND	FOOT	1380 △1					1380 △1		
*	X0326451	VIDEO SYSTEM DETECTION CAMERA	EACH	3						3	
	X0326486	DECORATIVE RAILING (PARAPET MOUNTED)	FOOT	639 △1		639 △1					
* *	X0326801	COMBINED SEWERS TO BE CLEANED	FOOT	253	253						
*	X0326968	JUNCTION BOX, POLE OR POST MOUNTED	EACH	9						9	
*	X0327004	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	2					2		
*	X0327172	REMOVE AND REPLACE SIGN AND SUPPORTS	EACH	1	1						
*	X0327371	PLUG EXISTING PIPE	CU YD	0.2	0.2						
	X6050040	REMOVING MANHOLES, SPECIAL	EACH	1					1		
*	X0370010	COAXIAL JUMPER CABLE (CDOT)	EACH	3						3	
*	X0370013	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER (CDOT)	EACH	1						1	
*	X0370014	CONCRETE FOUNDATION, 20" DIAMETER, 3/4" ANCHOR RODS, 13" BOLT CIRCLE (CDOT)	EACH	2						2	
*	X0370015	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/2" ANCHOR RODS, 16 1/2" BOLT CIRCLE (CDOT)	EACH	2						2	
*	X0370017	DRILL MANHOLE OR HANDHOLE, CHICAGO	EACH	4						4	
*	X0370018	ELECTRIC CABLE IN CONDUIT NO. 14, 19/C (CDOT)	FOOT	694						694	

* DENOTES SPECIALTY ITEM * * DENOTES NON-PARTICIPATING ITEM (100% STATE)

△1 Rev. 7-19-13

Rev.

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

D160W25-sht-500	DESIGNED - JWM	REVISED -	
USER NAME = pimsarno	DRAWN - JWM	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - AC	REVISED -	
PLOT DATE = 5/16/2013	DATE - 5/14/2013	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 15 OF 21 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	19

CONTRACT NO. 60W25

ILLINOIS FED. AID PROJECT

FILE PATH = pw:\\398839-pwint.aecomonline.local:PWAECOM01\Documents\01 Americas\Transportation\60260938 Circle\Phase II\0010 CAD\005 Roadway\Sheets\60W25 Contract\D160W25-sht-500