REMOVAL SCHEDULE

LOCATION	STATION	TO	STATION	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE BARRIER REMOVAL	PAVED SHOULDER REMOVAL	PARKING LOT PAVEMENT REMOVAL	REMOVE IMPACT ATTENUATORS, NO SALVAGE	APPROACH SLAB REMOVAL	FENCE REMOVAL
				ACRE	SQ YD	SQ YD	FOOT	FOOT	SQ FT	FOOT	SQ YD	SQ YD	EACH	SQYD	FOOT
MORGAN STREET	3602+45	TO	3606+85	-	988	26	-	492	2850	-	-	-	-	296	-
MORGAN STREET - UIC DRIVEWAY	3602+88	TO	3603+20	-	- 1	61	26	-	1 -	-	-	61	-	-	-
MORGAN STREET - DRIVEWAY	3606+35	TO	3606+52	-	-	22	-	-	-	-	-	-	-	-	-
CONGRESS PARKWAY	3305+50	TO	3306+63	- 1	473	-	-	310	1069	-	-	-	-	-	134
MORGAN STREET EXIT RAMP	1002+56	TO	1005+92	-	265	-	-	562	-	-	18	-	1	-	-
I-290 WESTBOUND	338+11	TO	340+60	-	-	-	-	155	-	248	346	-	-	-	148
I-290 EASTBOUND	338+25	TO	339+86	0.06	-	-	-	-	-	229	116	-	-	-	-
TOTAL				0.06	1726	109	26	1519	3919	477	480	61	1	296	282
ROUNDED TOTAL				0.25	1726	109	26	1519	3919	477	480	61	1	296	282

1 1

FILE PATH : pw:\\388039-pwint1.aecomonline.local:PWAECOM20\Documents\01 Americas\Transportation\60269938 Circle\Phase_II\000_CAD\006_Roadway\Sheets\60W25_Contract\D160W25-sht-Schedule-01

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

D160W25-sht-Schedule-01	DESIGNED - AFC	REVISED - 1 7/19/2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
USER NAME = ChiuA	DRAWN - AFC	REVISED -	
PLOT SCALE = 50.0000 ' / in.	CHECKED - DBM	REVISED -	
PLOT DATE = 7/14/2013	DATE - 6/17/2013	REVISED -	

SCHEDULE OF QUANTITIES

SCALE: | SHEET 1 OF 3 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	31
		CONTRACT NO. 60W25		
		ILLINOIS FED. AID PROJECT		