

BEAM 12

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
BK. S. ABUT.	3603+27.59	27.50'	595.70	595.70
CL. BRG. S. ABUT.	3603+29.09	27.50'	595.76	595.76
A	3603+39.09	27.50'	596.17	596.23
B	3603+49.09	27.50'	596.54	596.63
C	3603+59.09	27.50'	596.86	596.97
D	3603+69.09	27.50'	597.13	597.24
E	3603+79.09	27.50'	597.34	597.45
F	3603+89.09	27.50'	597.51	597.59
G	3603+99.09	27.50'	597.63	597.67
H	3604+09.09	27.50'	597.69	597.70
CL. PIER 1	3604+13.92	27.50'	597.72	597.72
I	3604+23.92	27.50'	597.77	597.75
J	3604+33.92	27.50'	597.82	597.80
K	3604+43.92	27.50'	597.87	597.85
L	3604+53.92	27.50'	597.92	597.90
M	3604+63.92	27.50'	597.96	597.95
N	3604+73.92	27.50'	597.97	597.95
O	3604+83.92	27.50'	597.93	597.92
CL. PIER 2	3604+86.92	27.50'	597.90	597.90
P	3604+96.92	27.50'	597.80	597.81
Q	3605+06.92	27.50'	597.64	597.71
R	3605+16.92	27.50'	597.43	597.53
S	3605+26.92	27.50'	597.18	597.29
T	3605+36.92	27.50'	596.87	596.98
U	3605+46.92	27.50'	596.51	596.61
V	3605+56.92	27.50'	596.11	596.18
W	3605+66.92	27.50'	595.67	595.68
CL. BRG. N. ABUT.	3605+71.76	27.50'	595.44	595.44
BK. N. ABUT.	3605+73.26	27.50'	595.38	595.38

FILE PATH: C:\Users\khalil\OneDrive\Documents\Drawings\60W25-513-Screen4.dwg

Entire sheet revised

HBM
 ENGINEERING GROUP, LLC
 CONSULTING & DESIGN
 INSPECTION & TESTING
 RESEARCH & TESTING
 4415 WEST HARRISON ST.
 SUITE 231
 HELLSTON, IL 60162
 PHONE: (708) 236-0900
 FAX: (708) 236-0901

0161709-60W25-513-Screen4.dwg
 USER NAME: willmardaus
 PLOT SCALE: 01.0000 1" = 10'
 PLOT DATE: 7/15/2013

DESIGNED - MI, LAB
 DRAWN - LAB
 CHECKED - MAI, MI, JJS
 DATE - 6/17/2013

REVISED - 07/19/2013 MI, LAP
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

TOP OF SLAB ELEVATIONS (SHEET 3 OF 3)
 STRUCTURE NO. 016-1709

SCALE: SHEET 51-13 OF 51 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	157
CONTRACT NO. 60W25			ILLINOIS FED. AID PROJECT	