

90% FED.  
10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	BRIDGE	RETAINING WALL	LIGHTING	TRAFFIC SIGNALS	UTILITY
				0004	0011	0040	0021	0021	0043
				URBAN	016-1709	016-1724	URBAN	URBAN	URBAN
* X0370021	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID (CDOT)	EACH	1					1	
* X0370022	ELECTRICAL HANDHOLE, HEAVY DUTY, 36", 24" FRAME AND LID (CDOT)	EACH	1					1	
* X0370023	ELECTRICAL MANHOLE, 3' X 4' X 4', 24" FRAME AND LID (CDOT)	EACH	2				1	1	
* X0370028	HARNESS CABLE, NO. 16 B/C (CDOT)	FOOT	340					340	
* X0370031	POLE, STEEL, ANCHOR BASE, 12-1/2" DIA. 3-GAUGE, 34' -6" (CDOT)	EACH	2					2	
* X0370042	VIDEO CABLE HARNESS (CDOT)	EACH	3					3	
* X0370044	VIDEO DETECTION POWER SUPPLY (CDOT)	EACH	1					1	
* X0370047	INSTALL LIGHT POLE, MAST ARM AND LUMINAIRE (CHICAGO)	EACH	10				10		
* X0370049	UNDERGROUND CONDUIT, PVC, 2" DIA., SCHEDULE 80 (CDOT)	FOOT	520				520		
* X0370050	ADVANCED TRANSPORTATION CONTROLLER, TRAFFIC, 16 LOAD BAY, P CABINET (CDOT)	EACH	1					1	
* X0370052	ELECTRIC CABLE IN CONDUIT NO. 4, 2/C (CDOT)	FOOT	97					97	
* X0370053	ELECTRIC CABLE IN CONDUIT, NO. 14 3/C, SHIELDED (CDOT)	FOOT	387					387	
* X0370054	INTERFACE PANEL, 4 CAMERA (CDOT)	EACH	1					1	
* X0370057	MAST ARM, STEEL, MONOTUBE 20 FT. (CDOT)	EACH	3					3	

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM

FILE PATH: c:\388937\p\1\ascom\1\m\local\p\ae\0\0\Documents\81\_American Transportation\6269938\_Circle Phase 1\A00\_CAD\008\_Roadway\Sheet\60W25\_Contract\0168W25-akt-500



D160W25-akt-500  
 USER NAME: pmasor/no  
 PLOT SCALE: 1:8000 1/4" = 1'-0"  
 PLOT DATE: 5/16/2013

DESIGNED - JWM  
 DRAWN - JWM  
 CHECKED - AC  
 DATE - 5/14/2013  
 REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCALE: SHEET 16 OF 21 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	20
CONTRACT NO. 60W25				
ILLINOIS FED. AID PROJECT				

Rev.