

FILE PATH = p:\388035\pmt\escomon\me\local\p\AECOM\0\Documents\01_Americas\Transportation\60269938_Circle\Phase_1\000_CAD\005_Roadway\Sheets\60W25-Contract\0160W25-sht-Drain-Schedule-94.dgn

PROPOSED PIPE SCHEDULE													
PIPE	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	UPSTREAM INVERT ELEVATION	DOWNSTREAM INVERT ELEVATION	STORM SEWERS, CLASS A, TYPE 1	STORM SEWERS, CLASS A, TYPE 2	STORM SEWER (WATER MAIN REQUIREMENTS)	VCP COMBINED SEWER (CDOT)	COMBINED SEWER (WATER MAIN REQUIREMENTS) (CDOT)			TRENCH BACKFILL (CY)	
					(FT)	(FT)	(FT)	(FT)	8"	8"	12"	24"	(CY)
					12"	12"	12"	8"	8"	12"	24"	(CY)	
MORGAN STREET													
P-01	S-01	S-02	589.28	589.23								1	
P-02	S-02	PR CONNECTION (STA. 3602+19.90 PR CL MORGAN ST)	588.99	584.90 (EX PIPE)							23	24	
P-03	S-03	PR CONNECTION (STA. 3602+23.53 PR CL MORGAN ST)	587.56	584.85 (EX PIPE)							23	23	
P-04	S-04	S-05	590.24	590.19							5	1	
P-05	S-05	PR CONNECTION (STA. 3602+71.17 PR CL MORGAN ST)	589.85	585.08 (EX PIPE)							23	17	
P-06A	EX PIPE (STA. 3306+31.13 PR CL CONGRESS PKWY)	S-06	585.38	584.79							54	71	
P-06B	S-06	EX PIPE (STA. 3602+67.67 PR CL MORGAN ST)	583.82	583.75							20	41	
WEST CONGRESS PARKWAY													
P-07	S-07	PR CONNECTION (STA. 3306+34.63 PR CL CONGRESS PKWY)	589.44	585.45 (EX PIPE)				13				9	
P-08	S-08	PR CONNECTION (STA. 3305+26.79 PR CL CONGRESS PKWY)	587.31	586.60 (EX PIPE)				13				8	
P-09	S-09	S-09A	589.15	589.10							5	1	
P-09A	S-09A	PR CONNECTION (STA. 3305+26.79 PR CL CONGRESS PKWY)	587.58	586.60 (EX PIPE)							8	3	
MORGAN STREET EXIT RAMP													
P-10	S-10	S-12	587.81	582.67		129						90	
P-11	S-11	S-12	586.11	585.85	26							5	
P-12	S-12	S-13	582.67	577.06		141						72	
P-13	S-13	EX STR (TSC 1115)	577.06	575.52		59						13	
WB I-290													
P-27	S-27	S-28	573.31	573.28	6							2	
P-28	S-28	EX STR (TSC1120)	573.20	573.05	33							8	
EB I-290													
P-29	S-29	EX STR (TSC1150)	572.68	572.50		18						7	
P-32	S-32	S-33	572.55	572.54	4							1	
P-33	S-33	EX STR (TSC565)	572.50	572.35			34					8	
TOTALS						69	347	34	26	92	54	20	405

- NOTES:
- PIPE AMOUNT PROVIDED AT LOCATIONS WHERE STRUCTURES ARE BEING REPLACED BUT EXISTING PIPES ARE NOT.
 - ADDITIONAL TRENCH BACKFILL QUANTITY PROVIDED ON THE DRAINAGE AND UTILITY PLAN SHEETS FOR STORM SEWER AND COMBINED SEWER REMOVAL.



DI60W25-sht-Drain-Schedule-04.dgn
 USER NAME = chitua
 PLOT SCALE = 50.0000' / in.
 PLOT DATE = 6/14/2013

DESIGNED - DMS	REVISED -
DRAWN - DMS	REVISED -
CHECKED - AFC	REVISED -
DATE - 6/17/2013	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

DRAINAGE SCHEDULES

SCALE: SHEET 4 OF 4 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-007R	COOK	317	37
CONTRACT NO. 60W25				
ILLINOIS FED. AID PROJECT				