

INDEX OF SHEETS

1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES AND HIGHWAY STANDARDS
3-4	SUMMARY OF QUANTITIES
5-5A.	OVERALL BULKHEAD AND CONCRETE FILL PLAN
6-8	STAGING AND TRAFFIC CONTROL PLANS
9	PLAN - LOCATION NO. 1 - VAN BUREN STREET
10	PLAN - LOCATION NO. 2 - HALSTED STREET
11	PLAN - LOCATION NO. 3 - HARRISON STREET
11A.	PLAN - LOCATION NO. 4 - GATESHAFT NO. 2
12	TUNNEL NOTES AND DETAILS
* 13-17	RECORD DRAWINGS - TUNNEL AND PUMP STATION
18-27	SOIL BORINGS
28	BD22 - PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
29	TC08 - ENTRANCE AND EXIT RAMP CLOSURE DETAILS
30	TC09 - SINGLE LANE WEAVE AND MULTI-LANE WEAVE
31	TC10 - TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
32	TC14 - TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
33	TC17 - PARTIAL RAMP AND SHOULDER CLOSURE DETAILS
34	TC22 - ARTERIAL ROAD INFORMATION SIGN
35-37	TC24 - CITY OF CHICAGO TYPICAL PAVEMENT MARKINGS

* Added 17A, 17B, 17C.

INDEX OF HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
000001-06	SYMBOLS, ABBREVIATION, AND PATTERNS
701101-03	OFF ROAD OPERATIONS - MULTILANE LESS THAN 15 FEET FROM EDGE OF PAVEMENT
701400-06	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701401-07	LANE CLOSURE FREEWAY/EXPRESSWAY
701411-08	MULTI-LANE, TRAFFIC CONTROL AND ENTRANCE OR EXIT RAMP
701446-04	TWO LANE CLOSURE, FREEWAY/EXPRESSWAY
701501-06	URBAN LANE CLOSURE 2L, 2W, UNDIVIDED
701606-08	URBAN LANE CLOSURE, MULTI LANE, 2W + MOUTABLE MEDIAN
701801-05	SIDEWALK CORNER OR CROSSWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CHICAGO DEPARTMENT OF WATER MANAGEMENT (CDWM) SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE OF CONSTRUCTION.

THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.

THE CONTRACTOR SHALL BE PROVIDED A FIELD OFFICE TO BE SHARED WITH ADJACENT CONSTRUCTION PROJECTS IN THE AREA.

10 FT (3 M) TRANSITIONS SHALL BE USED TO MATCH PROPOSED ITEMS OF WORK TO EXISTING ITEMS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEM OF WORK SPECIFIED.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE IDOT TRAFFIC CONTROL SUPERVISOR AT (847) 705-4155 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

THE RESIDENT ENGINEER SHALL CONTACT THE AREA TRAFFIC FIELD ENGINEER AT (847) 705-4412 A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACING THE PERMANENT PAVEMENT MARKINGS.

ALL PAVEMENT PATCHING AND SIDEWALK REPLACEMENT AREAS AFFECTED BY THE IMPROVEMENT LOCATIONS TO BE DETERMINED BY THE ENGINEER.

SAFE WORKING PRACTICES SHALL BE CONTINUOUSLY DEMONSTRATED BY THE CONTRACTOR. THE TUNNEL ENVIRONMENT IS TO BE CONSIDERED HOSTILE AND DUE CAUTION SHALL BE EXERCISED IN ALL MANNERS OF WORK PERFORMANCE AND INSPECTION. THE CONTRACTOR IS REQUIRED TO PREPARE AND SUBMIT A SAFETY AND DISINFECTION PLAN PRIOR TO ANY ENTRANCE INTO THE TUNNELS. THIS WORK SHALL NOT BE PAID FOR SEPARATELY, BUT INCLUDED IN THE COST OF BULKHEAD TUNNEL. (SPECIAL).

THE DRAWINGS HAVE BEEN PREPARED FROM EXISTING WATER TUNNEL PLANS WHICH HAVE NOT BEEN VERIFIED AS TO THEIR ACCURACY. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING EXISTING DIMENSIONS AND DETAILS ON THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

WATER TUNNEL LOCATIONS AND SUBSURFACE FEATURES SHOWN ARE BASED UPON ORIGINAL WATER TUNNEL DRAWINGS. EXISTING FEATURES ARE NOTED WHERE INFORMATION IS AVAILABLE.

ALL WATER TUNNEL ELEVATIONS ARE WITH RESPECT TO THE CITY OF CHICAGO DATUM (CCD). ALL PAVEMENT ELEVATIONS ARE WITH RESPECT TO NAV88. THE ELEVATION CORRELATION IS ELEV. 579.88 NAV88 = ELEV. 0.0 CCD

THE CONTRACTOR SHALL PERFORM ALL WORK IN FULL COMPLIANCE WITH OSHA STANDARDS AND REQUIREMENTS. IDOT'S STANDARD SPECIFICATION FOR ROAD AND BRIDGE CONSTRUCTION AND CHICAGO DEPARTMENT OF WATER MANAGEMENT REQUIREMENTS, AS APPLICABLE.

ALL LANDSCAPE AREA AFFECTED BY THE IMPROVEMENT SHALL BE RESTORED WITH TOPSOIL, NUTRIENTS, AND SEEDING AS DIRECTED BY THE ENGINEER.

GENERAL NOTES (CITY OF CHICAGO)

BEFORE STARTING ANY EXCAVATION WITHIN THE CITY OF CHICAGO, THE CONTRACTOR SHALL CONTACT "C.U.A.N." (CHICAGO UTILITY ALERT NETWORK) AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

FILE NAME = D:\2280\2280_21 - Circle Interchange Tunnel Bulkheading\CADD SHEETS\016R\25-INT-060.dgn



USER NAME = rgall	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' / 1"	DRAWN -	REVISED -
PLOT DATE = 4/12/2013	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, GENERAL NOTES, &
HIGHWAY STANDARDS

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
							90/94	0101.6-2P-1-3 (13)	COOK	37	2
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT											

Rev.

CONTRACT NO. 60W36