

LAKE COUNTY	SIGN PANEL TYPE 2				SIGN PANEL TYPE 1																									
	DO NOT ENTER (R5-1)		KEEP RIGHT (R4-7)		ILLINOIS RTE 2 DIGITS (M1-1100)		US RTE 2 DIGITS (M1-4)		CARDINAL DIRECTION (M3-1,2,3,4)		DIRECTIONAL ARROW (M6-2A)		WRONG WAY (R5-1A)		ONE WAY (R6-1L)		ONE WAY (R6-1R)		NO RIGHT TURN (R3-1)		NO LEFT TURN (R3-2)		RETROREFLECTIVE SIGN SUPPORT PANEL		TELESCOPING STEEL SIGN SUPPORT		BASE FOR TELESCOPING STEEL SIGN SUPPORT	REMOVE SIGN ASSEMBLY TYPE A	REMOVE SIGN PANEL TYPE 1	
	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY	SQ FT	QTY/TOTAL FT	(EA)	(EA)	(SQ FT)		
SB I-94 (TRI-STATE TOLLWAY) TO IL RTE 21 (MILWAUKEE AVE) (LOC. 1)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3	27	0	0.00	2	30	0	0	0
SB I-94 (TRI-STATE TOLLWAY) TO IL RTE 137 (BUCKLEY RD) (LOC. 2)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	9	0	0	0	0.00	0	0	0	0	22.5
NB I-94 (TRI-STATE TOLLWAY) TO IL RTE 137 (BUCKLEY RD) (LOC. 2)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	9	1	9	0	0.00	0	0	0	0	0
NB I-94 (TRI-STATE TOLLWAY) TO IL RTE 176 (PARK AVE) (LOC. 3)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	3	27	0	0.00	1	15	0	0	0
SB I-94 (TRI-STATE TOLLWAY) TO IL RTE 22 (HALF DAY RD) (LOC. 4)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	9	1	9	0	0.00	0	0	0	0	0
NB I-94 (TRI-STATE TOLLWAY) TO IL RTE 22 (HALF DAY RD) (LOC. 4)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	9	1	9	0	0.00	0	0	0	0	0
EB IL RTE 120 (BELVIDERE RD) TO IL RTE 21 (MILWAUKEE AVE) (LOC. 5)	1	16	0	0	1	9	0	0	1	4.5	1	4.375	4	35	1	6.75	1	6.75	0	0	0	0	5	4.17	5	78	1	0	8.75	
WB IL RTE 120 (BELVIDERE RD) TO IL RTE 21 (MILWAUKEE AVE) (LOC. 5)	2	32	0	0	1	9	0	0	1	4.5	1	4.375	4	35	1	6.75	1	6.75	0	0	0	0	5	4.17	5	78	1	0	8.75	
EB IL RTE 120 (BELVIDERE RD) TO GREENLEAF AVE (LOC. 6)	3	48	0	0	0	0	0	0	0	0	0	0	4	35	3	20.25	3	20.25	0	0	0	0	6	5.00	7	111	0	0	8.75	
WB IL RTE 120 (BELVIDERE RD) TO GREENLEAF AVE (LOC. 6)	1	16	0	0	0	0	0	0	0	0	0	0	2	17.5	1	6.75	2	13.5	0	0	0	0	2	1.67	2	30	0	0	0	
NB US RTE 41 (SKOKIE HWY) TO WASHINGTON ST (COUNTY A22) (LOC. 7)	2	32	0	0	0	0	0	0	0	0	0	0	2	17.5	2	13.5	2	13.5	0	0	0	0	3	2.50	4	55	0	1	0	
WASHINGTON ST (COUNTY A22) TO NB US RTE 41 (SKOKIE HWY) (LOC. 7)	2	32	0	0	0	0	1	9	1	4.5	1	4.375	2	17.5	1	6.75	1	6.75	0	0	0	0	2	1.67	2	25	1	0	0	
TOTAL	11	176	0	0	2	18	1	9	3	13.5	3	13.13	18	157.5	9	60.75	10	67.5	4	36	9	81	23	19.17	28	422	3	1	48.75	

NOTE:
RETROREFLECTIVE SIGN PANEL SHALL BE USED ON SIGN SUPPORTS
FOR 'DO NOT ENTER' AND 'WRONG WAY' SIGNS

FILE NAME =	USER NAME = SMITHCJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LAKE COUNTY SIGN SCHEDULE OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pwwork\pwwork\smithc\0340446\Design\Sheet-RampSignage-DuPageCo.dgn	DRAWN -	REVISED -	2013-024-SG			VARIOUS	90	12		
Default	CHECKED -	REVISED -	CONTRACT NO. 60W50							
PLOT SCALE = 100.0000' / 1" /	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
	PLOT DATE = 5/24/2013			SCALE:	SHEET	OF	SHEETS	STA.	TO	STA.