ROUTE	: Dundee Rd. (Wheeling Rd	l. to Wolf Rd.)					
CROSS	S STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPA
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
FROIVI	10	(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YI
Wolf Rd		(NB/SB)		12	15	180	20
vvoii Ru			2				
		WB	2	6	15	90	10
		WB	2	12	15	180	20
		WB	2	4	50	200	22
		WB	2	12	6	72	8
	Northgate Pkwy	WB	2	12	6	72	8
Northgate Pkwy	Wheeling Rd	WB	2	12	8	96	11
Wheeling Rd		EB	2	4	25	100	11
		EB	2	12	10	120	13
	Northgate Pkwy	EB	2	12	8	96	11
Northgate Pkwy		EB	2	6	50	300	33
		EB	1	12	8	96	11
		EB	2	12	8	96	11
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	8	96	11
	Wolf Rd	EB	2	12	8	96	11
		TOTALS:			252		226
					FT		SY

CROSS S	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REP/
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	ARE
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ Y
Milwaukee		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
	Sanders	EB	1	12	6	72	8
Condon		\A/D	1	12	6	70	
Sanders		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB WB	2	12 12	6	72 72	8

ROUTE	Palatine Express (Sande	rs Rd. to Milwau	kee Ave.)		(Continued)		
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
	Milwaukee	WB	2	12	6	72	8
		TOTALS:			222		296
					FT		SY

ROUTE:	Niles Center Rd. (Church	St. to Skokie B	lvd.)				
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Skokie Blvd		NB	1	3	20	60	7
		SB	1	3	20	60	7
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		CL	1	3	30	90	10
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		CL	1	3	100	300	33
		NB	1	3	100	300	33
		CL	1	3	300	900	100
		NB	1	3	100	300	33
		CL	1	3	200	600	67
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		SB	1	3	100	300	33
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		CL	1	3	300	900	100
		CL	1	3	100	300	33
		NB	1	3	20	60	7
		SB	1	3	20	60	7
		NB	1	3	30	90	10
		SB	1	3	30	90	10
		NB	1	3	40	120	13
	Church St	CL	1	3	100	300	33
		TOTALO			4000		000
		TOTALS:			1890		630
					FT		SY

FILE NAME =	USER NAME = tariqfm	DESIGNED -	REVISED -
c:\pw_work\pwidot\tariqfm\d0335178\HMA-(00K-N0RTH-Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 5/21/2013	DATE -	REVISED -

STATE	E OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

	INTERMITTENT RESURFACING SCHEDULE							
	DUNDEE	RD., P	ALATINE	EXPRESS,	AND	NILES	CENTER RD).
SCALE:		SHEET	OF	SHEETS	STA.		TO STA.	

F.A RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.
VAR.	2013-032 RS	COOK	37	12
		CONTRACT	NO. 6	0W68
	ILLINOIS FED. AI	D PROJECT		