ROUTE	Hibbard Rd. (Illinois Rd. to	Winnetka Rd.)					
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAI
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD
Illinois Rd		SB	1	10	6	60	7
		NB	1	20	12	240	27
		NB	1	12	15	180	20
		NB	1	12	12	144	16
		NB	1	12	6	72	8
		SB	1	12	6	72	8
		SB	1	15	3	45	5
		SB	1	15	3	45	5
		SB	1	3	12	36	4
		NB	1	16	15	240	27
		NB	1	8	8	64	7
		NB	1	10	15	150	17
		SB	1	10	15	150	17
	Longmeadow Rd	NB	2	6	10	60	7
Longmeadow Rd		NB	1	3	25	75	8
		SB	1	3	25	75	8
		SB	1	12	12	144	16
		NB	1	8	20	160	18
	Meadowview Dr	SB	1	15	10	150	17
Meadowview Dr		SB	1	12	10	120	13
	Winfield Dr	SB	1	5	20	100	11
Winfield Dr		SB	1	12	3	36	4
		SB	1	4	7	28	3
		SB	1	3	10	30	3
		SB	1	12	6	72	8
		SB	1	5	23	115	13
	Winnetka Rd	NB	1	5	23	115	13
		TOTALS:			332		310
					FT		SY

ROUTE:	Dempster St. (River Rd. to	Luther Ln.)					
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
1110111		(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD)
Luther Ln		WB	1,2	3	100	300	33
	Dee Rd	WB	1	3	20	60	7
Dee Rd	200114	WB	1,2	3	100	300	33
		WB	1,2	3	100	300	33
	Potter Rd	WB	1,2	3	25	75	8
Potter Rd		WB	1,2	3	100	300	33
		WB	2	3	100	300	33
		WB	1,2	3	50	150	17
		WB	1,2	3	100	300	33
	I-294	WB	2	3	40	120	13
I-294		WB	2	3	20	60	7
		WB	1,2	3	100	300	33
		WB	1,2	3	100	300	33
		WB	1,2	3	50	150	17
		WB	1,2	3	100	300	33
		WB	1	3	50	150	17
		WB	1,2	3	150	450	50
		WB	1	3	50	150	17
	River Rd	WB	1	3	50	150	17
River Rd		EB	1,2	3	100	300	33
		EB	1	3	50	150	17
		EB	2	3	12	36	4
	I-294	EB	1,2	3	20	60	7
I-294		EB	1,2	3	100	300	33
		EB	1,2	3	50	150	17
		EB	1,2	3	50	150	17
		EB	1,2	3	50	150	17
		EB	1,2	3	50	150	17
		EB	1,2	3	50	150	17
		EB	1,2	3	100	300	33
	Potter Rd	EB	1,2	3	50	150	17
Potter Rd		EB	1,2	3	50	150	17
		EB	1,2	3	100	300	33
	Dee Rd	EB	1,2	3	20	60	7
Dee Rd		EB	1,2	3	40	120	13
	Luther Ln	EB	1	3	10	30	3
		TOTALS:			2307		769
		TOTALO.			FT		SY

ROUTE: Sheridan Rd. (Lincoln St. to Sheridan Pl.)							
CROSS STREET		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Lincoln St		NB	1	10	3	30	3
		NB	2	10	3	30	3
		NB	1	10	63	630	70
	Milburn St	NB	2	10	63	630	70
Milburn St		NB	1	10	3	30	3
	Central Ave	NB	2	10	3	30	3
Central Ave		NB	1	14	3	42	5
		NB	1	10	3	30	3
		NB	2	10	3	30	3
		NB	2	3	25	75	8
		NB	1	10	3	30	3
		NB	2	10	3	30	3
	Clinton Ave	NB	1	10	3	30	3

CONTINUED ON NEXT SHEET

FILE NAME =	USER NAME = tariqfm	DESIGNED	=	REVISED -
c:\pw_work\pwidot\tariqfm\d0335178\HMA-	:00K-N0RTH-Design.dgn	DRAWN	-	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED	=	REVISED -
	PLOT DATE = 5/21/2013	DATE	-	REVISED -

SCALE:

	INTER	MITTENT R	ESURFAC	ING	SCHEDULE	F.A RTE.
HIRE	RARD R	IN DEMPS	TFR ST	ΔND	SHERIDAN RD.	VAR.
IIIDI	יו טוואכ	ID., DLIVII 3	ILII 31.,	AND	SILIIDAN IID.	
	SHEET	OF	SHEETS	STA.	TO STA.	

F.A RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
VAR.	2013-032 RS	соок	37	13			
		CONTRACT	NO. 6	OW68			
	ILLINOIS FED. AID PROJECT						