CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
TROW	10	(NB/SB)	(1, 2, 3)	WDTH	LENGTH	(SQ FT)	(SQ YD)
West of Naperville Rd		WB	1	12	8	96	11
vvoor or raperville ra		WB	1	12	4	48	5
		WB	1	13	4	52	6
		WB	1	12	16	192	21
		WB	1, 2	3	100	300	33
		WB	1, 2	3	80	240	27
		WB	2	12	8	96	11
		WB	1, 2	3	15	45	5
		WB	1	12	3	36	4
		WB	1, 2	3	125	375	42
		WB	2	12	16	192	21
		WB	1, 2	3	95	285	32
		WB	2	3	70	210	23
		WB	2	3	120	360	40
		WB	LT	12	3	36	4
	Lambert Rd	WB	1	12	3	36	4
Lambert Rd		WB	2	17	3	51	6
		WB	2	7	3	21	2
		WB	2	7	3	21	2
		WB	2	7	3	21	2
		WB	2	8	3	24	3
		WB	2	3	150	450	50
		WB	2	12	4	48	5
		WB	2	3	15	45	5
		WB	2	12	4	48	5
		WB	2	3	15	45	5
		WB	2	12	4	48	5
		WB	2 2	3 12	12	36	4
		WB WB	2	3	4 20	48 60	5 7
		WB	2	12	4	48	5
		WB		3	25	75	8
		WB	2	12	3	36	4
		WB	2	12	4	48	5
		WB	2	12	4	48	5
		WB	2	12	6	72	8
	Hilliard Dr	WB	2	6	4	24	3
Hilliard Dr	Timala Di	WB	2	6	4	24	3
		WB	2	12	3	36	4
	1	WB	2	5	6	30	3
		WB	1	12	4	48	5
	Bridge	WB	2	12	4	48	5
Bridge	1	EB	1	12	6	72	8
		EB	2	12	3	36	4
		EB	2	12	4	48	5
		EB	2	6	3	18	2
		EB	2	6	3	18	2
		EB	2	12	55	660	73
	Hilliard Dr	EB	2	5	50	250	28
Hilliard Dr		EB	1	12	3	36	4
		EB	1, 2	3	50	150	17
		EB	2	12	10	120	13
		EB	LT	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	4	48	5
		EB	2	12	4	48	5
		EB	2	12	4	48	5

ROUTE:	US 20 (Shales Pkwy. to 1/	4 mile west of	Naperville	Rd./Elizabet	th Dr.)		(Continued)
CROSS	STREET	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
TROW	10	(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Lambert Ln	+	EB	1	12	6	72	8
Eumbert En	+	EB	2	12	6	72	8
	+	EB	2	3	70	210	23
	+	EB	2	3	82	246	27
		EB	1	12	4	48	5
	<u> </u>	EB	2	12	6	72	8
		EB	2	3	80	240	27
		EB	2	12	4	48	5
	+	EB	2	3	90	270	30
	<u> </u>	EB	1, 2	3	55	165	18
		EB	1	12	4	48	5
		EB	1	12	6	72	8
		EB	1, 2	3	80	240	27
	+	EB	1, 2	12	4	48	5
	+	EB	2	12	4	48	5
	+	EB	1, 2	3	50	150	17
	+	EB	2	12	6	72	8
	+	EB	1	12	4	48	5
	+	EB	2	12	4	48	5
	+	EB	1	12	3	36	4
		EB	2	12	3	36	4
	<u> </u>	EB	1	3	35	105	12
		EB	1	6	3	18	2
		EB	1	12	4	48	5
		EB	2	12	4	48	5
		EB	2	3	30	90	10
		EB	1	12	3	36	4
		EB	2	12	3	36	4
		EB	2	3	65	195	22
		EB	2	12	10	120	13
		EB	2	3	65	195	22
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	8	96	11
		EB	2	12	8	96	11
		EB	1	12	3	36	4
		EB	1	12	3	36	4
		EB	2	12	6	72	8
		EB	1	12	3	36	4
	West of Naperville Rd	EB	2	12	3	36	4
		TOTALS:			2034		1059
					FT		SY

FILE NAME =	USER NAME = tariqfm	DESIGNED -	REVISED -
c:\pw_work\pwidot\tariqfm\d0335178\HMA-(	:00K-N0RTH-Design.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -
	PLOT DATE = 5/21/2013	DATE -	REVISED -

STATE OF ILLINOIS							
DEPARTMENT	0F	TRANSPORTATION					

SCALE:

INTERMITTENT RESURFACING SCHEDULE				F.A SECTION		COUNTY	TOTAL SHEETS	SHEET NO.		
US 20		VAR.	2013-032 RS	COOK	37	27				
			03 20					CONTRACT	NO. 6	0W68
	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				