

## NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL (2) SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = tariqfm	DESIGNED -	REVISED - R. MIRS 09-15-97	<u>.</u>	ARTERIAL ROAD			F.A	SECTION	COUNTY	TOTAL SH SHEETS	ξĒΤ.
c:\pw_work\pwidot\tariqfm\d0335178\	ØW68-DistStd.dgn	DRAWN -	REVISED - R. MIRS 12-11-97	STATE OF ILLINOIS				VAR.	2013-032 RS	соок	37	35
	PLOT SCALE = 100.0000 '/ in.	CHECKED -	REVISED -T. RAMMACHER 02-02-99		INFORMATION SIGN  SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.				TC-22	CONTRACT	NO. 60W	68
	PLOT DATE = 5/21/2013	DATE -	REVISED - C. JUCIUS 01-31-07					FED. ROAD	DIST. NO. 1   ILLINOIS FED. A	ILLINOIS FED. AID PROJECT		$\neg$