

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	GRAND TOTAL	0021 90% FED 10% STATE <i>HSIP</i> TOTAL QUANTITY	0005 80% FED 20% STATE <i>F</i> TOTAL QUANTITY
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	33		33
30300106	AGGREGATE SUBGRADE IMPROVEMENT 6"	SQ YD	34,293	34,293	
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1715	1715	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	6391	6391	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	31,985	31,985	
X4060110	BITUMINOUS MATERIALS (PRIME COAT), <i>SPECIAL</i>	<i>POUNDS</i>	91,027.1	91,027.1	
40600300	AGGREGATE (PRIME COAT)	TON	115.1		115.1
40600525	LEVELING BINDER (HAND METHOD), N50	TON	30.0		30.0
40600627	LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N50	TON	4255		4,255
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	460		460
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	410		410
40600990	TEMPORARY RAMP	SQ YD	80		80
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7324		7324
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1696		1696
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	276		276
44000100	PAVEMENT REMOVAL	SQ YD	2242	2242	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	447		447
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1956	1956	
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	366		366
44200124	PAVEMENT PATCHING, TYPE III, 10 INCH	SQ YD	45		45
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	58		58
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	697		697

22

• SPECIALTY ITEMS

FILE NAME *	USER NAME * granton	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\granton\0201271\0207	11-sht-schedule.dgn	DRAWN -	REVISED -			599	(B3MFT & 103MFT)W	ROCK ISLAND	340	4	
	PLOT SCALE * 100.0000 / in.	CHECKED -	REVISED -								
Default	PLOT DATE * Wed Mar 28 10:54:46 2013	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
ILLINOIS FED. AID PROJECT											

Rev.