

SCHEDULE OF QUANTITIES

35300400 PORTLAND CEMENT CONCRETE BASE COURSE 9"

SQ_YD	LOCATION	WIDTH	REMARKS
4523.6	RT Sta. 802+90.0 TO 868+48.0	6.208	
40.0	RT Sta. 868+48.0 TO 869+60.0	3.208	Sideroad
2214.2	RT Sta. 869+60.0 TO 901+70.0	6.208	
40.0	RT Sta. 901+70.0 TO 902+82.0	3.208	Sideroad
923.0	RT Sta. 902+82.0 TO 916+20.0	6.208	
110.1	RT Sta. 916+20.0 TO 916+93.0	Var	Guardrail terminal
220.2	RT Sta. 916+93.0 TO 918+92.0	9.958	Guardrail section
110.1	RT Sta. 918+92.0 TO 919+64.0	Var	Guardrail terminal
129.0	RT Sta. 919+64.0 TO 921+51.0	6.208	
36.4	RT Sta. 921+51.0 TO 922+53.0	3.208	Sideroad
1707.9	RT Sta. 922+53.0 TO 947+29.0	6.208	
41.4	RT Sta. 947+29.0 TO 948+45.0	3.208	Sideroad
27.0	RT Sta. 948+45.0 TO 948+84.0	6.208	
110.1	RT Sta. 948+84.0 TO 949+57.0	Var	
208.1	RT Sta. 949+57.0 TO 951+45.0	9.958	
106.3	RT Sta. 952+23.0 TO 953+19.0	9.958	
110.1	RT Sta. 953+19.0 TO 953+91.0	Var	
1313.4	RT Sta. 953+91.0 TO 972+95.0	6.208	
36.4	RT Sta. 972+95.0 TO 973+97.0	3.208	Sideroad
1494.8	RT Sta. 973+97.0 TO 995+64.0	6.208	
558.1	RT Sta. 997+03.0 TO 1005+12.0	6.208	
35.0	RT Sta. 1005+12.0 TO 1006+10.0	3.208	Sideroad
809.8	RT Sta. 1006+10.0 TO 1017+84.0	6.208	
31984.6	TOTAL		

40600525 LEVELING BINDER (HAND METHOD) .N50

ION	LOCATION	REMARKS
30.0	ENTIRE JOB	
30.0	TOTAL	

44000100 PAYEMENT REMOVAL

SQ_YD	LOCATION	REMARKS
239.0	LT Sta. 948+70.0 TO 951+64.6	
386.0	LT Sta. 952+47.0 TO 957+62.0	
249.0	RT Sta. 948+55.0 TO 951+40.0	
313.0	RT Sta. 952+24.5 TO 957+63.0	
311.0	LT Sta. 992+97.0 TO 995+64.0	
285.0	LT Sta. 997+03.0 TO 999+19.0	
166.0	RT Sta. 993+71.0 TO 995+64.0	
101.0	RT Sta. 997+03.0 TO 998+33.0	
96.0	LT Sta. 1014+97.0 TO 1017+84.0	
96.0	RT Sta. 1014+97.0 TO 1017+84.0	
2242.0	TOTAL	

44000500 COMBINATION CURB AND GUTTER REMOVAL

EQFT	LOCATION	REMARKS
960.0	RT Sta. 802+90.0 TO 812+50.0	INCLUDING GUTTER OUTLETS
996.0	RT Sta. 814+38.0 TO 824+34.0	INCLUDING GUTTER OUTLETS
1956.0	TOTAL	

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

EQFT	LOCATION	REMARKS
29710.0	LT & RT Sta 802+90.0 TO 951+45.0	Placed on level binder
8642.0	LT & RT Sta 952+43.0 TO 995+64.0	Placed on level binder
4162.0	LT & RT Sta 997+03.0 TO 1017+84.0	Placed on level binder
42514.0	TOTAL	

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

EACH	LOCATION	OFFSET	REMARKS
1	RT Sta. 960+54.0	34	Concrete ditch check
1	TOTAL		

542D0217 PIPE CULVERTS, CLASS D, TYPE 1 12"

EQFT	LOCATION	OFFSET	REMARKS
96.0	LT Sta. 992+42.0	37	Two 48' Pipes
30.0	RT Sta. 1005+56.0	33	Verify size of existing in field
126.0	TOTAL		

542D0220 PIPE CULVERTS, CLASS D, TYPE 1 15"

EQFT	LOCATION	OFFSET	REMARKS
40.0	LT Sta. 920+40.0	37	
38.0	LT Sta. 927+73.0	52	
46.0	LT Sta. 943+19.0	35	
38.0	LT Sta. 944+00.0	33	
34.0	LT Sta. 944+95.0	32	
34.0	LT Sta. 945+58.0	32	
99.0	LT Sta. 955+10.0	27	
92.0	LT Sta. 956+09.0	27	
36.0	LT Sta. 964+82.0	52	
34.0	LT Sta. 966+94.0	47	
40.0	LT Sta. 969+34.0	42	
32.0	LT Sta. 973+55.0	41	
48.0	LT Sta. 984+91.0	38	
38.0	LT Sta. 994+31.0	29	
58.0	LT Sta. 1015+78.0	27	