

SCHEDULE OF QUANTITIES

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA.

EACH	LOCATION	OFFSET	REMARKS
1.0	RT Sta. 811+68.0	38	Pipe coming from house
<u>3.0</u>			Contingency quantity
4.0	TOTAL		

61133200 FIELD TILE JUNCTION VAULTS, 3' DIA.

EACH	LOCATION	OFFSET	REMARKS
1.0	RT Sta. 977+09.0	38	PVC Pipes outlet into ditch
<u>1.0</u>	RT Sta. 977+46.0	38	PVC Pipe outlet into ditch
2.0	TOTAL		

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS

FOOT	LOCATION	REMARKS
1500.0	LT Sta. 806+77.3 TO 821+77.3	
175.0	LT Sta. 832+13.3 TO 833+88.3	
125.0	LT Sta. 843+82.3 TO 845+07.3	
175.0	LT Sta. 856+37.3 TO 858+12.3	
137.5	LT Sta. 865+71.0 TO 867+08.5	
112.5	LT Sta. 869+62.5 TO 870+75.0	
<u>75.0</u>	LT Sta. 899+97.5 TO 900+72.5	
2300.0	TOTAL	

63000370 LONG-SPAN GUARDRAIL OVER CULVERT, 25 FT SPAN

FOOT	LOCATION	REMARKS
175.0	LT Sta. 917+04.5 TO 918+79.5	
<u>175.0</u>	RT Sta. 917+04.5 TO 918+79.5	
350.0	TOTAL	

63100169 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED

EACH	LOCATION	REMARKS
1	LT Sta. 806+27.3 TO 806+77.3	Departure
1	LT Sta. 821+77.3 TO 822+27.3	Approach
1	LT Sta. 831+63.3 TO 832+13.3	Departure
1	LT Sta. 833+88.3 TO 834+38.3	Approach
1	LT Sta. 843+32.3 TO 843+82.3	Departure
1	LT Sta. 845+07.3 TO 845+57.3	Approach
1	LT Sta. 855+87.3 TO 856+37.3	Departure
1	LT Sta. 858+12.3 TO 858+62.3	Approach
1	LT Sta. 865+21.0 TO 865+71.0	Departure
1	LT Sta. 867+08.5 TO 867+58.5	Approach
1	LT Sta. 869+12.5 TO 869+62.5	Departure
1	LT Sta. 870+75.0 TO 871+25.0	Approach
1	LT Sta. 899+47.5 TO 899+97.5	Departure
1	LT Sta. 900+72.5 TO 901+22.5	Approach
1	LT Sta. 916+54.5 TO 917+04.5	Departure
1	LT Sta. 918+79.5 TO 919+29.5	Approach
1	RT Sta. 916+54.5 TO 917+04.5	Departure
<u>1</u>	RT Sta. 918+79.5 TO 919+29.5	Approach
18.0	TOTAL	

63301210 REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A

FOOT	LOCATION	REMARKS
100.0	LT Sta. 950+20.9 TO 951+20.9	
125.0	LT Sta. 952+90.7 TO 954+15.7	
125.0	RT Sta. 949+71.3 TO 950+96.3	
37.5	RT Sta. 952+66.8 TO 953+04.3	
<u>100.0</u>	LT Sta. 996+92.5 TO 997+92.5	
487.5	TOTAL	

63301215 REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE B

FOOT	LOCATION	REMARKS
12.5	LT Sta. 996+30.0 TO 996+42.5	
<u>25.0</u>	LT Sta. 996+67.5 TO 996+92.5	
37.5	TOTAL	

63301235 REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES

FOOT	LOCATION	REMARKS
<u>25.0</u>	LT Sta. 996+42.5 TO 996+67.5	
25.0	TOTAL	

63302700 REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6

EACH	LOCATION	REMARKS
1	LT Sta. 951+20.9 TO 951+64.6	
1	LT Sta. 952+47.0 TO 952+90.7	
1	RT Sta. 950+96.3 TO 951+40.0	
<u>1</u>	RT Sta. 952+23.0 TO 952+66.8	
4	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	REMARKS
1	LT Sta. 806+27.3	Departure
1	LT Sta. 807+04.0	Culvert Headwall
1	LT Sta. 812+19.0	Culvert Headwall
1	LT Sta. 822+27.3	Approach
1	LT Sta. 831+63.3	Departure
1	LT Sta. 832+82.0	Culvert Headwall
1	LT Sta. 834+38.3	Approach
1	LT Sta. 843+32.3	Departure
1	LT Sta. 844+26.0	Culvert Headwall
1	LT Sta. 845+57.3	Approach