

ENTRANCE SCHEDULE

LOCATION	NEW ENT. TYPE	RT	HMA	NOTE	** TOTAL	** TOTAL	TOTAL	TOTAL	TOTAL	TOTAL	TOTAL	4060110	35101400	42300300	40800050	40600985	44000200
					AGG	HMA	NEW CONC	OLD CONC	AGG	HMA	NEW CONC	*BIT	AGG	PCC DRVW	INC	*PCC SURF	DRIVEWAY
					AREA	AREA	AREA	AREA	AREA	AREA	AREA	PRIME	BASE CSE	PVMT	HMA	REM-BUTT	PVMT
					SO FT	SO FT	SO FT	SO FT	SO YD	SO YD	SO YD	POUND	TON	7"	TON	SO YD	SO YD
														SY			
IL 92																	
806+38	PE/MB	RT	HMA		1097.0	974.0		605.0	121.9	108.2							18.18
811+83	PE/MB	RT	HMA		933.0	822.0			103.7	91.3							15.34
812+22	Between Driveways	RT	HMA		130.0	97.0			14.4	10.8							1.81
812+59	PE	RT	HMA		738.0	665.0			82.0	73.9							12.41
814+82	PE/MB	RT	CONC/BIT	Conc Apron - Conc Rem Included If needed - House may be removed	539.0	75.0	406.0	267.0	59.9	8.3	45.1	2.38	27.28	45.11			1.40
823+95	CE	LT	None	Remove Entrance to Boat Ramp													
824+67	FRONTAGE PE	RT	HMA		1226.0	1073.0			136.2	119.2							20.03
826+68	PE/MB	RT	HMA		1014.0	878.0			112.7	97.6							16.39
829+26	PE/MB	RT	HMA		1040.0	904.0			115.6	100.4							16.87
832+06	PE/MB	RT	HMA		993.0	856.0			110.3	95.1							15.98
833+27	PE/MB	RT	HMA		986.0	849.0			109.6	94.3							15.85
834+62	PE/MB	RT	HMA		1198.0	1062.0			133.1	118.0							19.82
838+07	PE/MB	RT	HMA		1053.0	916.0			117.0	101.8							17.10
842+49	PE/163rd St W	RT	HMA	12" agg. 3" inc HMA	1311.0	1175.0			145.7	130.6							21.93
847+70	FE	RT	AGG	Clear Driveway to ROW	1344.0				149.3								
851+69	FE	RT	AGG	Clear Driveway to ROW	1392.0				154.7								
860+86	FE	RT	AGG	Clear Driveway to ROW	1341.0				149.0								
864+37	FE	RT	AGG	Clear Driveway to ROW	1344.0				149.3								
867+57	FE	RT	AGG	Clear Driveway to ROW	1341.0				149.0								
869+10	154th St W	RT	HMA	12" agg. 3" inc HMA	2453.0	2311.0			272.6	256.8							43.14
874+38	PE/MB	RT	HMA		1254.0	1060.0			139.3	117.8							19.79
874+55	MB	LT	HMA		216.0	141.0			24.0	15.7							2.63
876+59	PE/MB	RT	HMA		1231.0	1037.0			136.8	115.2							19.36
876+59	MB	LT	HMA		216.0	141.0			24.0	15.7							2.63
884+05	CE	LT	HMA	Park	1422.0	1338.0			158.0	148.7							24.98
888+66	FE	RT	AGG		1166.0				129.6								
890+82	CE/MB	RT	HMA		1165.0	1057.0			129.4	117.4							19.73
893+95	CE/MB	RT	HMA	Lodge	1020.0	913.0			113.3	101.4							17.04
896+25	CE	LT	HMA	Park	1140.0	1055.0			126.7	117.2							19.69
896+59	PE/MB	RT	HMA		816.0	709.0			90.7	78.8							13.23
901+62	CE	LT	HMA	Park	948.0	874.0			105.3	97.1							16.31
902+34	147th St W	RT	HMA	12" agg. 3" inc HMA	3146.0	2951.0			349.6	327.9							55.09
914+87	PE/MB	RT	HMA		1205.0	1012.0			133.9	112.4							18.89
914+87	MB	LT	HMA		219.0	143.0			24.3	15.9							2.67
920+44	PE/MB	LT	HMA		898.0	799.0			99.8	88.8							14.91
922+04	144th St W	RT	HMA	12" agg. 3" inc HMA	3378.0	3150.0			375.3	350.0							58.80
922+47	MB	LT	HMA		224.0	149.0			24.9	16.6							2.78
923+49	PE	RT	HMA		809.0	744.0			89.9	82.7							13.89
923+51	PE/MB	LT	HMA		1298.0	1114.0			144.2	123.8							20.79
924+57	NEW FE	RT	AGG		1072.0				119.1								
927+73	PE/MB	LT	HMA		1166.0	1009.0			129.6	112.1							18.83
932+00	NEW FE	RT	AGG		876.0				97.3								
933+82	PE/MB	RT	HMA		730.0	633.0			81.1	70.3							11.82
934+02	Frontage PE/MB	LT	HMA		724.0	627.0			80.4	69.7							11.70
943+13	Frontage PE/MB	LT	HMA	Conc Apron	1477.0	1375.0		460.0	164.1	152.8							25.67
943+16	Frontage PE/MB	RT	HMA	Conc Apron	1180.0	1066.0		1044.0	131.1	118.4							19.90
943+62	MB between driveways	LT	HMA		127.0	95.0			14.1	10.6							1.77
944+02	PE	LT	HMA		1220.0	1120.0			135.6	124.4							20.91
944+50	Between Driveways	LT	HMA		187.0	137.0			20.8	15.2							2.56
944+97	PE	LT	HMA		1023.0	920.0			113.7	102.2							17.17
945+26	Between Driveways	LT	HMA		92.0	69.0			10.2	7.7							1.29