

## SUMMARY OF QUANTITIES

LOCATION OF WORK:	LOCATION #1 F.A.P. ROUTE 719 U.S. 150	LOCATION #2 F.A.P. ROUTE 804 PROSPECT AVE
COUNTY:	CHAMPAIGN URBAN PATCHING	CHAMPAIGN URBAN PATCHING
FUNDING BREAK OUT:	100% STATE	100% STATE
CONSTRUCTION TYPE CODE:	0005	0005

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
44022039	PARTIAL DEPTH REMOVAL 5 1/2"	SQ YD	150.0	0.0	150.0
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	731.0	731.0	0.0
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	153.0	153.0	0.0
44201299	DOWEL BARS, 1 1/2"	EACH	1881.0	1881.0	0.0
44213100	PAVEMENT FABRIC	SQ YD	153.0	153.0	0.0
44213200	SAW CUTS	FOOT	5529.0	5529.0	0.0
44213204	TIE BARS, 3/4"	EACH	125.0	125.0	0.0
67100100	MOBILIZATION	L SUM	1.0	0.8	0.2
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	0.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	0.0	1.0
X4421000	PARTIAL DEPTH PATCHING	TON	47.0	0.0	47.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	5.0	0.0	5.0

\* F.A.P. 719 & F.A.P. 804

FILE NAME *	USER NAME * baker	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\puidot\baker\140349555\0570	137-shl-500.dgn	DRAWN -	REVISED -		SCALE:	SHEET 1	OF 1	SHEETS	STA.	TO STA.	CHAMPAIGN	9	4
	PLOT SCALE * 40.0000 / / in.	CHECKED -	REVISED -		CONTRACT NO. 70A37								
#MODELNAME*	PLOT DATE * 5/22/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								