

URBAN

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE	
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY	BRIDGE
				RURAL	RURAL
				F. A. U. 7706	SN 054-0512
55100900	STORM SEWER REMOVAL 18"	FOOT	495	495	
55101200	STORM SEWER REMOVAL 24"	FOOT	257	257	
58700300	CONCRETE SEALER	SQ FT	1974		1974
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	155		155
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	9	9	
60105000	PIPE DRAINS, CORRUGATED STEEL OR ALUMINUM ALLOY 12"	FOOT	30	30	
60107600	PIPE UNDERDRAINS 4"	FOOT	2967	2967	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	209	209	
60500040	REMOVING MANHOLES	EACH	9	9	
60500060	REMOVING INLETS	EACH	26	26	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6. 24	FOOT	3730.5	3730.5	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2937.5	2937.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	

*SPECIALTY ITEM

LAST SAVED : 5/23/2013
 PEN TABLE : VB-Half.tbl
 PLOT DRIVER : TR-Y&mf-B&ack-Half.plt

FILE NAME : \\06103\Cad\1\Plans\003.0672789\Sht-5.dgn	USER NAME : jepettibona	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 7 OF 10 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7706	23(B-1)	LOGAN	179	10
BUS. LOOP 55 OVER SALT CREEK		CONTRACT NO. 72789		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		