

STORM SEWER REMOVAL SCHEDULE								
LOCATION	TRENCH BACKFILL	STORM SEWER REMOVAL					REMOVING MANHOLES	REMOVING INLETS
		8 IN	12 IN	15 IN	18 IN	24 IN		
	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
Business Loop 55 over Salt Creek								
83+39.00 TO 83+39.00	2.1		6					
83+39.00 TO 85+13.00	107.6				173			
85+11.00 TO 85+13.00	10.6		28					
85+13.00 TO 85+13.00	2.0		6					
85+13.00 TO 85+13.00	2.1		4					
85+13.00 TO 86+73.00	98.9				158			
85+13.00 TO 86+77.00	97.1			165				
86+73.00 TO 86+73.00	1.7		5					
86+73.00 TO 88+39.00	105.3				164			
86+75.00 TO 86+77.00	7.0		28					
86+77.00 TO 86+77.00	1.7		8					
86+77.00 TO 88+40.00	97.1			164				
88+23.00 TO 88+39.00	8.1			17				
88+38.00 TO 88+40.00	7.2		28					
88+39.00 TO 90+71.00	175.8					229		
88+40.00 TO 88+40.00	0.8		3					
88+40.00 TO 90+23.00	113.6			184				
89+93.00 TO 90+22.00	12.9	35						
90+22.00 TO 90+23.00	2.3		5					
90+23.00 TO 90+45.00	7.3		32					
90+23.00 TO 90+45.00	8.1			32				
90+68.00 TO 90+69.00	16.1		34					
90+71.00 TO 90+86.00	11.4					28		
92+08.00 TO 92+09.00	13.2		28					
92+09.00 TO 92+09.00	5.9		22					
93+23.00 TO 93+25.00	15.3		57					
93+83.00 TO 93+84.00	10.4		28					
93+84.00 TO 93+84.00	6.7		22					
95+28.00 TO 95+30.00	8.4		35					
95+34.00 TO 95+36.00	15.0		35					
95+36.00 TO 95+40.00	13.1			44				
95+72.00 TO 95+75.00	8.2		32					
103+33.00 TO 104+95.00	45.9		162					
104+95.00 TO 90+22.00	11.1	35						
104+95.00 TO 104+97.00	24.3		62					
104+95.00 TO 105+26.00	11.3		31					
112+82.00 TO 112+91.00	25.4			94				
83+39.00	8.1					1	1	
85+11.00	2.7						1	
85+13.00	16.6					2	2	
86+73.00	8.3					1	1	
86+75.00	2.7						1	
86+77.00	8.9					1	1	
88+23.00	3.9						1	
88+38.00	2.8						1	
88+40.00	14.1					2	1	
90+22.00	11.2					1	1	
90+68.00	4.6						1	
90+69.00	4.7						1	
90+71.00	5.4					1		
92+08.00	3.7						1	
92+09.00	5.8						1	
93+23.00	3.7						1	
93+83.00	2.6						1	
93+84.00	5.3						1	
95+28.00	4.0						1	
95+34.00	4.0						1	
95+36.00	5.1						1	
95+72.00	5.1						1	
104+95.00	7.9						2	
112+91.00	7.4						2	
TOTAL	1259.6	70	701	700	495	257	9	26
	USE 1260							

CONCRETE REMOVAL SCHEDULE					
LOCATION	SIDE	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	CONCRETE BARRIER REMOVAL	SLOPE WALL REMOVAL
		SQ YD	FOOT	FOOT	SQ YD
Business Loop 55 over Salt Creek					
73+00.67 TO 73+98.92	RT		104		
73+00.67 TO 73+99.50	LT		103		
76+36.90 TO 79+25.60	RT		286		
76+99.24 TO 79+35.97	LT		242		
76+99.48 TO 79+35.97	RT		241		
77+03.26 TO 79+28.12	LT		227		
79+27.89 TO 79+96.80	LT	133			
79+48.94 TO 79+95.05	RT	67			
79+86.23 TO 84+19.21	LT		436		
79+86.23 TO 84+19.79	RT		436		
79+95.31 TO 93+00.00	RT		1305		
79+99.46 TO 93+00.00	LT		1301		
84+28.00 TO 95+83.00	LT/RT			1155	
91+00.00 TO 93+00.00	LT/RT	1381			
95+87.00 TO 96+08.00	-				230
102+79.00 TO 102+99.00	-				250
103+05.00 TO 113+88.00	LT/RT			1083	
105+00.00 TO 106+56.05	LT/RT	1135			
122+66.49 TO 123+28.56	RT	168			
122+75.48 TO 123+31.64	LT/RT	142			
TOTAL		3026	4681	2238	480

SIGN REMOVAL SCHEDULE					
LOCATION	SIDE	TYPE	LEGEND	REMOVE SIGN PANEL TYPE I	REMOVE GROUND MOUNTED SIGN SUPPORT
				SQ FT	EACH
Business Loop 55 over Salt Creek					
79+42	56' LT	R1-1	"STOP"	6	1
		R6-3	"DIVIDED HIGHWAY"	5	
79+86	45' RT	R1-1	"STOP"	6	1
		R6-3	"DIVIDED HIGHWAY"	5	
90+42	41' RT	R2-1	"SPEED LIMIT 55"	5	1
90+55	34' LT	R2-1	"SPEED LIMIT 45"	5	1
94+21	39' RT	-	"SALT CREEK"	6	1
103+12	36' LT	-	"SALT CREEK"	6	1
113+88	0' LT	OM-3L		3	1
114+47	1' LT	R4-7	"KEEP RIGHT"	5	1
		OM1-1		2	
		OM1-1		2	
122+10	111' RT	R1-1	"STOP"	6	1
123+25	48' RT	R1-1	"STOP"	6	1
		R6-3a	"DIVIDED HIGHWAY"	5	
TOTAL				73	10

TREE REMOVAL SCHEDULE		
LOCATION	TREE REMOVAL	
	ACRE	
Business Loop 55 over Salt Creek		
78+00.00 TO 84+00.00	0.01	
84+00.00 TO 90+00.00	0.94	
90+00.00 TO 96+00.00	1.51	
96+00.00 TO 102+00.00	1.55	
102+00.00 TO 108+00.00	1.45	
108+00.00 TO 114+00.00	0.45	
114+00.00 TO 120+00.00	0.25	
120+00.00 TO 124+50.00	0.01	
TOTAL	6.17	
	PAY 6.25	

LAST SAVED = 5/23/2013 4:31:39 PM
 PEN TABLE = V:\H4\F\H4
 PLOT DRIVER = TR-18pdf-Block-Half.plt

FILE NAME =	USER NAME = jepettibone	DESIGNED -	REVISED -
i:\06103\cad\l\plans\005.D672789-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 5/23/2013 4:31:39 PM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES			
STORM SEWER REMOVAL, CONCRETE REMOVAL, SIGN REMOVAL, & TREE REMOVAL			
SCALE: NONE	SHEET NO. 4 OF 5 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7706	23(B-1)	LOGAN	179	27
BUS. LOOP 55 OVER SALT CREEK			CONTRACT NO. 72789	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				