

SEEDING SCHEDULE										
LOCATION		SIDE	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING	
			ACRE	POUND	POUND	POUND	TON	ACRE	POUND	
Business Loop 55 over Salt Creek										
74+00.00	TO	78+00.00	LT	0.05	5	5	5	0.1	0.11	5
74+00.00	TO	78+00.00	RT	0.08	7	7	7	0.2	0.15	8
78+00.00	TO	84+00.00	LT	0.16	14	14	14	0.3	0.25	16
78+00.00	TO	84+00.00	RT	0.26	23	23	23	0.5	0.41	26
84+00.00	TO	90+00.00	LT	0.54	49	49	49	1.1	0.54	54
84+00.00	TO	90+00.00	RT	0.65	59	59	59	1.3	0.91	65
90+00.00	TO	96+00.00	LT	0.52	47	47	47	1.0	0.92	52
90+00.00	TO	96+00.00	RT	1.21	109	109	109	2.4	2.42	121
96+00.00	TO	102+00.00	LT	1.15	104	104	104	2.3	2.24	115
96+00.00	TO	102+00.00	RT	0.97	87	87	87	1.9	1.94	97
102+00.00	TO	108+00.00	LT	1.34	121	121	121	2.7	2.68	134
102+00.00	TO	108+00.00	RT	1.20	108	108	108	2.4	2.40	120
108+00.00	TO	114+00.00	LT	0.70	63	63	63	1.4	1.41	70
108+00.00	TO	114+00.00	RT	1.10	99	99	99	2.2	2.20	110
114+00.00	TO	120+00.00	LT	0.55	50	50	50	1.1	1.10	55
114+00.00	TO	120+00.00	RT	0.60	54	54	54	1.2	1.21	60
120+00.00	TO	124+50.00	LT	0.22	20	20	20	0.4	0.45	22
120+00.00	TO	124+50.00	RT	0.40	36	36	36	0.8	0.80	40
Parking Lot with Large Pond Option										
				1.84	166	166	166	3.7	3.68	184
TOTAL				13.54	1221	1221	1221	27.0	25.82	1354
				PAY 13.50				PAY 25.75	PAY 1350	
Parking Lot with Small Pond Option										
				1.53	138	138	138	3.1	3.05	153

Note: Small Pond Option shown for Informational purposes

RIPRAP SCHEDULE						
LOCATION		SIDE	STONE RIPRAP, CLASS A5 SQ YD	STONE DUMPED RIPRAP		FILTER FABRIC SQ YD
				CLASS A3 TON	CLASS A4 TON	
Business Loop 55 over Salt Creek						
88+35	TO	91+34	RT		356	711
90+88	TO	98+68	LT		650	1300
94+57	TO	94+97	RT		86	171
98+50	TO	98+64	RT		9	19
100+22	TO	102+79	LT		200	399
100+31	TO	102+96	RT		189	377
104+91	TO	105+00	RT		35	70
105+12	TO	110+92	RT			808
Bridge Abutments and Piers		LT/RT	5175	404		6426
TOTAL				5175	404	1525
						10281

PERIMETER EROSION BARRIER SCHEDULE				
LOCATION		SIDE	PERIMETER EROSION BARRIER FOOT	
Business Loop 55 over Salt Creek				
76+00	TO	79+00	LT	304
80+00	TO	82+00	LT	202
80+00	TO	82+00	RT	197
88+00	TO	88+11	RT	11
91+34	TO	94+56	RT	312
98+60	TO	99+14	RT	63
98+66	TO	99+15	LT	52
99+74	TO	101+55	LT	220
99+82	TO	100+37	RT	60
101+75	TO	115+37	LT	1418
104+98	TO	121+85	RT	1813
115+54	TO	122+38	LT	679
122+50	TO	126+00	LT	350
123+01	TO	126+00	RT	305
TOTAL				5986

AGGREGATE (EROSION CONTROL) SCHEDULE			
LOCATION	SIDE	TYPE	AGGREGATE (EROSION CONTROL) TON
Business Loop 55 over Salt Creek			
88+90	RT	Extruding	4
89+68	RT	Extruding	4
90+50	RT	Extruding	4
91+30	RT	Extruding	4
91+98	LT	Extruding	4
92+45	RT	Flush	3
94+31	RT	Flush	3
95+00	LT	Extruding	4
95+50	RT	Flush	3
95+75	LT	Extruding	4
96+50	LT	Extruding	4
98+44	RT	Flush	3
98+64	LT	Extruding	4
100+27	LT	Extruding	4
100+36	RT	Extruding	4
102+87	RT	Extruding	4
103+00	LT	Flush	3
104+66	RT	Flush	3
105+00	LT	Flush	3
107+00	RT	Flush	3
110+00	RT	Flush	3
113+00	RT	Flush	3
116+00	RT	Flush	3
119+00	RT	Flush	3
122+05	RT	Flush	3
TOTAL			87

INLET AND PIPE PROTECTION SCHEDULE		
LOCATION	OFFSET	INLET AND PIPE PROTECTION EACH
Business Loop 55 over Salt Creek		
94+91.50	40' RT	1
96+30.00	32' RT	1
102+35.00	180' LT	1
102+56.00	32' RT	1
104+95.00	32' RT	1
115+46.00	96' LT	1
122+44.00	70' LT	1
TOTAL		7

EARTH EXCAVATION FOR EROSION CONTROL SCHEDULE			
LOCATION	SIDE	TYPE	EARTH EXCAVATION FOR EROSION CONTROL CU YD
Business Loop 55 over Salt Creek			
92+36	RT	Sed. Basin	4
94+40	RT	Sed. Basin	4
98+34	RT	Sed. Basin	4
122+14	RT	Sed. Basin	4
TOTAL			16

HEAVY DUTY EROSION CONTROL BLANKET SCHEDULE				
LOCATION	SIDE	HEAVY DUTY EROSION CONTROL BLANKET SQ YD		
Business Loop 55 over Salt Creek				
82+00	TO	88+00	RT	2454
82+00	TO	91+00	LT	3474
95+00	TO	97+00	LT	266
102+28	TO	102+42	LT	12
115+36	TO	115+35	LT	15
122+36	TO	122+51	LT	17
122+38	TO	122+54	RT	17
TOTAL				6255

LAST SAVED = 5/23/2013 4:31:39 PM
 PEN TABLE = V:\H4\1434
 PLOT DRIVER = TR-18pdf-Block-Half.plt

FILE NAME =	USER NAME = jpettibone	DESIGNED -	REVISED -
I:\06103\cad\t\plans\005.D672789-Sht-Schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 5/23/2013 4:31:39 PM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SEEDING, RIPRAP, AGGREGATE (EROSION CONTROL), INLET AND PIPE PROTECTION, PERIMETER EROSION BARRIER, EARTH EXCAVATION FOR EROSION CONTROL, & HEAVY DUTY EROSION CONTROL BLANKET			
SCALE: NONE	SHEET NO. 5 OF 5 SHEETS	STA.	TO STA.

F.A.U. RE. 7706	SECTION 23(B-1)	COUNTY LOGAN	TOTAL SHEETS 179	SHEET NO. 28
BUS. LOOP 55 OVER SALT CREEK			CONTRACT NO. 72789	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				