

INDEX OF SHEETS

1. COVER
2. INDEX OF SHEETS, GENERAL NOTES, AND HIGHWAY STANDARDS
3. SUMMARY OF QUANTITIES
4. LOCATION MAP
5. TYPICAL SECTIONS

HIGHWAY STANDARDS

- 701001-02 OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY FROM EDGE OF PAVEMENT
 701501-06 URBAN LANE CLOSURE 2L, 2W, UNDIVIDED
 701901-02 TRAFFIC CONTROL DEVICES
 780001-03 TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
2. NO EXCAVATION IS ANTICIPATED ON THIS PROJECT. SHOULD ANY EXCAVATION BE REQUIRED, J.U.L.I.E. SHALL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE (800) 892-0123.
3. THE AGGREGATE GRADATION FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CA-16 OR CA-20.
4. AGGREGATE FOR THE A-1 BITUMINOUS SURFACE TREATMENT SHALL BE CRUSHED LIMESTONE.
5. SHORT-TERM PAVEMENT MARKING SHALL BE PAINT - TAPE WILL NOT BE ALLOWED.
6. PERMANENT PAVEMENT MARKINGS SHALL NOT BE APPLIED UNTIL 10 DAYS AFTER THE AGGREGATE HAS BEEN APPLIED.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED <u>5/20</u> 20 <u>13</u>	<u>Bill M. Ben</u> ENGINEER OF OPERATIONS
EXAMINED <u>APRIL 26</u> 20 <u>13</u>	<u>Jimmy J. J.</u> ENGINEER OF PROJECT IMPLEMENTATION
EXAMINED <u>April 30</u> 20 <u>13</u>	<u>ORMI</u> ENGINEER OF PROGRAM DEVELOPMENT

FILE NAME *	USER NAME * anorptd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS AND GENERAL NOTES	F.A.P. S.B.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S:\CONTRACTMAINT_CAD\72625\INDO-STD-SIGN.dgn		DRAWN -	REVISED -			666/24	06 SEAL COAT SANG. CO.2014-1	SANGAMON	5	2
Default	PLOT SCALE = 1.0000" / In.	CHECKED -	REVISED -		SCALE:					
	PLOT DATE = May-21-2013 06:33:54AM	DATE -	REVISED -		SHEET 1 OF 1 SHEETS					CONTRACT NO. 72625
					STA. TO STA.					ILLINOIS FED. AID PROJECT