

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				ROADWAY 0005
20200100	EARTH EXCAVATION	CU YD	115	115
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5
40600300	AGGREGATE (PRIME COAT)	TON	3	3
40600990	TEMPORARY RAMP	SQ YD	243	243
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	252.4	252.4
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	316.9	316.9
44004250	PAVED SHOULDER REMOVAL	SQ YD	672	672
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	54	54
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	75	75
48101200	AGGREGATE SHOULDERS, TYPE B	TON	94	94
48203057	HOT-MIX ASPHALT SHOULDERS, 15"	SQ YD	939	939
48203100	HOT-MIX ASPHALT SHOULDERS	TON	377	377
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	8	8
60100072	SHOULDER REMOVAL AND REPLACEMENT 5"	FOOT	989	989
60107600	PIPE UNDERDRAINS 4"	FOOT	1978	1978
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	186	186
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	1978	1978

FILE NAME =	USER NAME = keyps	DESIGNED -	REVISED -
c:\pwork\pwork\keyps\d0348068\d076g	keyps	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55/70	60-10RS-2	MADISON	12	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76054	