

COUNTY:	WILLIAMSON	
LOCATION:	URBAN	
ROUTE:	F. A. P. 331 (IL 13)	
FUNDING:	80% FEDERAL 20% STATE	
WORK TYPE:	ROADWAY	SAFETY
CONSTRUCTION TYPE CODE	0003	0021

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	238	238	
* 72900100	METAL POST - TYPE A	FOOT	330	330	
* 72900200	METAL POST - TYPE B	FOOT	453	453	
* 73000100	WOOD SIGN SUPPORT	FOOT	120	120	
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	17	17	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	800	800	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27683	27683	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1996	1996	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	531	531	
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	873	873	
* 78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	18260	18260	
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	225	225	
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	193	193	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	708	708	
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	10	10	

*SPECIALTY ITEM

FILE NAME : 0978258-sh1-500-11.dgn
CH2MHILL.

USER NAME : mfo	DESIGNED - KN	REVISED -
PLOT SCALE : 2.0000 / in.	DRAWN - AS	REVISED -
PLOT DATE : 3/11/2013	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 11 OF 16 SHEETS STA. TO STA.

F.A.P. RTE. 331	SECTION (1-4R-2, N-4, TS-4)	COUNTY WILLIAMSON	TOTAL SHEETS 381	SHEET NO. 16
DRAWING NO. S00-11		CONTRACT NO. 78258		
ILLINOIS FED. AID PROJECT				