

COUNTY:	WILLIAMSON	
LOCATION:	URBAN	
ROUTE:	F. A. P. 331 (IL 13)	
FUNDING:	80% FEDERAL 20% STATE	
WORK TYPE:	ROADWAY	SAFETY
CONSTRUCTION TYPE CODE	0003	0021

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY		
* 78201000	TERMINAL MARKER - DIRLCT APPLIED	EACH	2	2	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1950	1950	
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	1000		1000
* 80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1		1
* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	746		746
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	376		376
* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	172		172
* 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	190		190
* 81028400	UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	94		94
* 81400100	HANDHOLE	EACH	16		16
* 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	3407		3407
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI -MOUNT, 250 WATT	EACH	10		10
* 82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	1		1
* 83062730	LIGHT POLE, WEATHERING STEEL 45 FT. M.H., TENON MOUNT	EACH	2		2
* 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	2		2

*SPECIALTY ITEM