

PAVEMENT AND SHOULDER SCHEDULE

LOCATION			HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90 TON	HOT-MIX ASPHALT PAVEMENT FULL-DEPTH 10 3/4" SO YD	HOT-MIX ASPHALT PAVEMENT FULL-DEPTH 15 1/4" SO YD	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" JOINTED SO YD	PROTECTIVE COAT SO YD	SAW CUTS FOOT	AGGREGATE SHOULDERS, TYPE A 4" SO YD	HOT-MIX ASPHALT SHOULDERS, 4" SO YD	HOT-MIX ASPHALT SHOULDERS, 15 1/4" SO YD	REMARKS
STATION	TO	STATION										
IL 13 WESTBOUND												
441+90.26	-	464+16.40			3,889			2,234			1,573	ALL AREAS TAKEN FROM MICROSTATION TRAVEL LANES AND SHOULDERS
464+16.40	-	468+62.25				1,095	1,095	446		228		
468+62.25	-	480+37.10			3,299			1,185		1,471		
455+65.23	-	460+11.57						450		361		
IL 13 EASTBOUND												
443+90.94	-	464+00.05			4,025			2,018			1,406	TRAVEL LANES AND SHOULDERS
464+00.05	-	467+95.22				966	966	395		58		
467+95.22	-	479+50.00			1,703			1,164		1,446		
450+50.11	-	460+11.57						965		768		
IL 13 MEDIAN												
460+11.57	-	464+00.05			1,191			777				MEDIAN AND TURN LANES
464+00.05	-	468+62.25				1,467	1,467	924				
468+62.25	-	472+61.62			799			682		95		
PLAZA DRIVE WEST												
8+30.00	-	11+51.32	164							317		TRAVEL, TURN LANES, AND SHOULDERS
COMMERCIAL DRIVE												
0+87.53	-	2+25.67	61									TRAVEL, TURN LANES, AND SHOULDERS
CITY STREET NORTHWEST												
0+11.04	-	5+31.56	224							433		TRAVEL, TURN LANES, AND SHOULDERS
CITY STREET NORTH												
0+51.32	-	3+25.26	190							110		TRAVEL, TURN LANES, AND SHOULDERS
CITY STREET SOUTHWEST												
0+10.13	-	3+99.79	192							281		TRAVEL, TURN LANES, AND SHOULDERS
CITY STREET SOUTH												
0+52.30	-	3+02.38	170									TRAVEL, TURN LANES, AND SHOULDERS
DIVISION STREET NORTH												
0+12.00	-	3+50.66				2,954	2,954					TRAVEL, TURN LANES, AND SHOULDERS
3+50.66	-	4+96.33		1,229								
4+96.33	-	18+34.56		2,957				2,677				
DIVISION STREET SOUTH												
1+00.00	-	3+04.77				1,992	1,992					TRAVEL, TURN LANES, AND SHOULDERS
3+04.77	-	8+00.00		3,288								
8+00.00	-	16+91.90		1,469				1,376				
NORTH FRONTAGE ROAD												
0+20.00	-	22+55.43	1,033									TRAVEL, TURN LANES, AND SHOULDERS SHARED USE PATH
0+53.07	-	22+55.43										
TIPPY ROAD												
8+04.75	-	9+76.73	58									TRAVEL, TURN LANES, AND SHOULDERS
LAKE SHORE DRIVE												
0+15.02	-	1+50.00	62									TRAVEL, TURN LANES, AND SHOULDERS
SHEET TOTALS			2,153	8,944	14,906	8,473	8,473	15,294		1,141	7,406	

▲ REVISED 6-5-13

FILE NAME: c:\pwworkspace\brandon.je\9335666\078258-sch-03.dgn	USER NAME: brandon.je	DESIGNED: KN	REVISED: SHEET	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT AND SHOULDER SCHEDULE	F.A.P. RTE. 331	SECTION (1-4R-2, N-4, TS-4)	COUNTY WILLIAMSON	TOTAL SHEETS 381	SHEET NO. 45
CH2MHILL	PLT SCALE: 2.0000 1" = 20'	DRAWN: AS	REVISIONS:							
	PLT DATE: 5/27/2013	CHECKED:	DATE:		SCALE:	SHEET NO. 3 OF 45 SHEETS		STA. TO STA.	DRAWING NO. SCH-03 CONTRACT NO. 78258 ILLINOIS FED. AID PROJECT	