

## SIDEWALK SCHEDULE

LOCATION			PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	DETECTABLE WARNINGS	REMARKS
STATION	TO	STATION	SQ FT	SQ FT	SQ FT	
<b>DIVISION ST NORTH</b>						
2+00.41	-	2+58.47	257.6		50.0	
3+00.94	-	3+37.18	162.7		50.0	
3+71.47	-	4+35.16	297.6		50.0	
4+62.81	-	5+49.44	497.2		50.0	
6+15.07	-	7+39.06	643.0		25.0	
7+51.07	-	8+36.92	396.7			
8+48.92	-	9+18.01	313.6		25.0	
9+68.09	-	10+39.78	326.6		25.0	
10+55.79	-	11+37.03	373.9			
11+51.02	-	12+23.04	330.5		25.0	
12+63.19	-	13+33.05	335.0		50.0	
13+68.22	-	14+10.22	208.6		50.0	
14+47.39	-	14+72.32	123.6		50.0	
15+09.48	-	15+41.82	160.6		50.0	
15+78.99	-	16+49.40	337.2		25.0	
16+63.52	-	17+75.33	531.6			
17+90.39	-	18+34.56	197.4			
<b>NORTH FRONTAGE ROAD</b>						
0+53.07	-	22+55.43		22,046.0		
<b>PROJECT TOTALS</b>			<b>5,493.5</b>	<b>22,046.0</b>	<b>525.0</b>	

## RIPRAP SCHEDULE

LOCATION			STONE DUMPED RIPRAP, CLASS A4	REMARKS
STATION	TO	STATION	SQ YD	
<b>IL 13</b>				
442+80.00	LT		8	
443+00.00	LT		38	
448+08.00	RT		13	
451+72.00	RT		13	
452+85.00	RT	- 455+70.00	611	
471+25.00	LT		5	
471+25.00	RT		13	
<b>CITY STREET NORTH</b>				
1+73.00	RT		9	
1+62.00	LT		8	
2+00.00	RT		20	
<b>CITY STREET SOUTH</b>				
5+55.00	-	7+45.00	396	
<b>CITY STREET NORTHWEST</b>				
0+92.00	RT		6	
1+14.00	LT		5	
<b>CITY STREET SOUTHWEST</b>				
0+95.00	RT		12	
1+00.00	LT		9	
<b>DIVISION STREET NORTH</b>				
6+45.00	LT		50	
16+00.00	LT		28	
<b>DIVISION STREET SOUTH</b>				
1+71.00			7	
3+03.00			7	
3+90.00			28	
<b>NORTH FRONTAGE ROAD</b>				
1+60.00	LT		7	
4+05.00	LT		7	
5+87.00	LT		7	
9+00.00	LT		7	
13+50.00	LT		7	
15+00.00	LT		7	
22+55.00	LT		34	
22+55.00	RT		27	
<b>BRENTWOOD DRIVE</b>				
9+42.00	RT		4	
<b>KIRK LANE</b>				
1+16.00	LT		4	
2+82.00	RT		4	
<b>PROJECT TOTALS</b>			<b>1,401</b>	