

GUARDRAIL SCHEDULE

LOCATION			STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS FOOT	TRAFFIC BARRIER TERMINAL, TYPE 2 EACH	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT EACH	GUARDRAIL MARKERS, TYPE B EACH	TERMINAL MARKER- DIRECT APPLIED EACH	REMARKS
STATION	TO	STATION						
IL 13 WESTBOUND								
458+71.17	-	458+83.67		1				
458+83.67	-	465+61.37	712.0			5		
465+61.37	-	465+69.09			1		1	
IL 13 EASTBOUND								
456+64.52	-	457+14.52			1		1	
457+14.52	-	463+39.19	625.0			5		
463+39.19	-	463+51.69		1				
PROJECT TOTALS			1,337.5	2	2	10	2	

SEEDING SCHEDULE

LOCATION			SEEDING, CLASS 1A ACRE	SEEDING, CLASS 2 ACRE	SEEDING, CLASS 7 ACRE	TEMPORARY EROSION CONTROL SEEDING POUND	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	MULCH METHOD 2 ACRE	REMARKS
STATION	TO	STATION									
IL 13											
440+98.39	-	461+00.00		2.39	2.39	120.00	430.20	215.10	215.10	4.78	
461+00.00	-	481+00.00		3.27	3.27	164.00	588.60	294.30	294.30	6.54	
DIVISION STREET SOUTH											
0+00.00	-	9+00.00	0.18	0.51	0.69	35.00	124.20	62.10	62.10		EROSION CONTROL BLANKET USED INSTEAD OF MULCH, METHOD 2. SEE SCH-34
9+00.00	-	16+00.00	0.16		0.16	8.00	28.80	14.40	14.40		EROSION CONTROL BLANKET USED INSTEAD OF MULCH, METHOD 2. SEE SCH-34
DIVISION STREET NORTH											
0+00.00	-	8+00.00	0.13	0.18	0.31	16.00	55.80	27.90	27.90		EROSION CONTROL BLANKET USED INSTEAD OF MULCH, METHOD 2. SEE SCH-34
8+00.00	-	18+38.55	0.34	0.11	0.45	23.00	81.00	40.50	40.50		EROSION CONTROL BLANKET USED INSTEAD OF MULCH, METHOD 2. SEE SCH-34
CITY STREET SOUTHWEST											
0+00.00	-	4+12.91		0.79	0.79	40.00	142.20	71.10	71.10	1.58	
CITY STREET NORTHWEST											
0+00.00		5+00.00		0.84	0.84	42.00	151.20	75.60	75.60	1.68	
CITY STREET NORTH											
0+00.00		3+52.51		0.33	0.33	17.00	59.40	29.70	29.70	0.66	
NORTH FRONTAGE ROAD											
0+00.00		22+60.06		2.43	2.43	122.00	437.40	218.70	218.70	4.86	
KIRK LANE											
0+00.00		7+00.00	0.40	0.47	0.87	44.00	156.60	78.30	78.30	1.74	
PROJECT TOTALS			1.25	11.25	12.50	631	2,255	1,128	1,128	21.75	

NOTES:

- FOR ADDITIONAL QUANTITY FOR TEMPORARY EROSION CONTROL SEEDING, SEE DRAWING NO. SCH-34.

FILE NAME =
D978258-sh-t-SCH-08.dgn

CH2MHILL

USER NAME = mfox

PLOT SCALE = 2.0000' / in.

PLOT DATE = 3/11/2013

DESIGNED - KN

DRAWN - AS

CHECKED -

DATE -

REVISED -

REVISED -

REVISED -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GUARDRAIL AND SEEDING SCHEDULE

SCALE:

SHEET NO. 8 OF 45 SHEETS

STA.

TO STA.

F.A.P.
RTE.

331

(1-4)R-2, N-4, TS-4

SECTION

COUNTY

WILLIAMSON

CONTRACT NO. 78258

TOTAL
SHEETS

381

SHEET
NO.

50

ILLINOIS FED. AID PROJECT