

## CURB AND GUTTER SCHEDULE

LOCATION			PROTECTIVE COAT	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	CONCRETE MEDIAN SURFACE 4 INCH	CONCRETE MEDIAN, TYPE SM-6.24	CLASS SI CONCRETE (OUTLET)	REMARKS
STATION	TO	STATION	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	CY	
<b>PLAZA DRIVE EAST</b>													
RT	100+61.91	-	100+93.81	23		79.5							
LT	100+05.15	-	100+26.35	21		74.5							
<b>BRENTWOOD LANE</b>													
RT	7+87.43	-	8+10.21	7		24.5							
RT	8+68.04	-	9+15.29	13		47.0							
RT	9+29.18	-	9+39.78	8								3.4	
RT	9+26.37	-	9+82.97	21		73.5							
LT	9+62.16	-	9+86.35	14		49.5							
<b>COMMERCE DRIVE</b>													
RT	19+54.92	-	19+79.95	13		45.5							
LT	19+51.20	-	19+84.63	16		56.0							
<b>SHEET TOTALS</b>			<b>136</b>	<b>0.0</b>	<b>0.0</b>	<b>450.0</b>	<b>0.0</b>	<b>0.0</b>	<b>0.0</b>	<b>0</b>	<b>0</b>	<b>3.4</b>	
<b>SHEET TOTALS FROM PVMNT SCH 3</b>			<b>8473</b>										
<b>SHEET TOTALS FROM C&amp;G SCH 9</b>			<b>2975</b>	<b>72.0</b>	<b>432.5</b>	<b>1006.0</b>	<b>3188.5</b>	<b>361.0</b>	<b>360.0</b>	<b>5036</b>	<b>6301</b>	<b>22.3</b>	
<b>SHEET TOTALS FROM C&amp;G SCH 10</b>			<b>4072</b>	<b>1861.5</b>	<b>188.0</b>	<b>10093.1</b>	<b>156.5</b>	<b>0.0</b>	<b>0.0</b>	<b>320</b>	<b>1421</b>	<b>31.3</b>	
<b>PROJECT TOTAL</b>			<b>15656</b>	<b>1933.5</b>	<b>620.5</b>	<b>11549.1</b>	<b>3345.0</b>	<b>361.0</b>	<b>360.0</b>	<b>5356</b>	<b>7722</b>	<b>57.0</b>	

**NOTES:**

- FOR ADDITIONAL QUANTITY FOR COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 AND TYPE B-6.24, SEE DRAWING NO. SCH-15.

FILE NAME = D978258-sh1-SCH-11.dgn

**CH2MHILL**

USER NAME = mfox

DESIGNED - KN

REVISED -

DRAWN - AS

REVISED -

PLOT SCALE = 2.0000' / 1" =

CHECKED -

REVISED -

PLOT DATE = 3/11/2013

DATE -

REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**CURB AND GUTTER SCHEDULE**

SCALE:

SHEET NO. 11 OF 45 SHEETS

STA.

TO STA.

F.A.P. RTE.

331

SECTION

(1-4)R-2, N-4, TS-4

COUNTY

WILLIAMSON

TOTAL SHEETS

381

SHEET NO.

53

DRAWING NO. SCH-11

CONTRACT NO. 78258

ILLINOIS FED. AID PROJECT