

SUMMARY OF QUANTITIES

ROUTE NO.	SECTION	COUNTY	SHEET NO.	TOTAL SHEETS
KICKAPOO TRAIL	08-F3000-03-BT	VERMILION	4	69
STA.		TO STA.		
F.H.W.A. REC.		ILLINOIS PROJECT		

ITEM	ITEM NAME	UNIT	QUANTITY	ITEM	ITEM NAME	UNIT	QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	2.75				
20400800	FURNISHED EXCAVATION	CU YD	2802	66300105	CALCIUM CHLORIDE APPLIED	TON	4.3
21101610	TOPSOIL FURNISH AND PLACE, 3"	SQ YD	13381	* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	935
25100630	EROSION CONTROL BLANKET	SQ YD	11048	* Δ 66900530	SOIL DISPOSAL ANALYSIS	EACH	1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	242	* Δ 66901001	REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN	L SUM	1
28000305	TEMPORARY DITCH CHECKS	FOOT	42	* Δ 66901002	ON-SITE MONITORING OF REGULATED SUBSTANCES	CAL DA	14 Δ
28000400	PERIMETER EROSION BARRIER	FOOT	3049	* Δ 66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1
28000500	INLET AND PIPE PROTECTION	EACH	4	67100100	MOBILIZATION	L SUM	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	11	Δ 72000100	SIGN PANEL - TYPE 1	SQ FT	59
28200200	FILTER FABRIC	SQ YD	11	Δ 72900100	METAL POST - TYPE A	FOOT	150
35100500	AGGREGATE BASE COURSE, TYPE A, 6"	SQ YD	200	Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	42
35102100	AGGREGATE BASE COURSE, TYPE B, 9"	SQ YD	7101	Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	80
* 40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	450	* K1005421	SEEDING (SPECIAL)	ACRE	6
* 40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	45	* X0322135	BOLLARD, QUICK RELEASE	EACH	3
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	34	* X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	12,864
42400300	PCC SIDEWALK 6"	SQ FT	150	* X0327009	REMOVE SIGN (SPECIAL)	EACH	5
42400800	DETECTABLE WARNINGS	SQ FT	54	* X0327395	IDENTIFICATION AND DISPOSAL OF EXISTING RAILROAD TIES	L SUM	1
48102100	AGG WEDGE SHLD TYPE B	TON	220	* X5537900	STORM SEWERS TO BE CLEANED, 15"	FOOT	50
50105220	PIPE CULVERT REMOVAL	FOOT	65	* X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
50300225	CONCRETE STRUCTURES	CU YD	8.5	* Z0012754	STRUCT. REPAIR OF CONC. (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	200
50300255	CONCRETE SUPERSTRUCTURE	CU YD	14.9	* Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	200
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3220	* Z0013798	CONSTRUCTION LAYOUT	L SUM	1
542D0220	PIPE CULV., CLASS D, TYPE 1 15"	FOOT	70	* Δ Z0078002	WOOD RAIL, SPECIAL	FOOT	96
542D0223	PIPE CULV., CLASS D, TYPE 1 18"	FOOT	102	* Δ XX000882	WOOD FENCE	FOOT	1,149
* 54213450	END SECTIONS, 15"	EACH	1	* XX002007	AGGREGATE BICYCLE PATH	SQ YD	7,101
* 54213453	END SECTIONS, 18"	EACH	4	# Z0076600	TRAINEES	Hour	1,000
				# Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	Hour	1,000

* SEE SPECIAL PROVISIONS

* SEE SPECIAL PROVISIONS Δ SPECIALTY ITEMS #0042

Δ Revised 7/17/19