



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 19, 2024

SUBJECT FAP Route 326 (IL 47)  
Project NHPP-B4N8(422)  
Section FAP 0326 22 BJ2  
McHenry County  
Contract No. 62T02  
Item No. 10, August 8, 2024 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page i of the Table of Contents to the Special Provisions
3. Revised pages 6, 20, & 21 of the Special Provisions
4. Revised sheets 2-6 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

**TABLE OF CONTENTS**

LOCATION OF PROJECT ..... 1

DESCRIPTION OF PROJECT ..... 1

MAINTENANCE OF ROADWAYS (D1) ..... 2

PUBLIC CONVENIENCE AND SAFETY (D1) ..... 2

STATUS OF UTILITIES (D1) ..... 2

TRAFFIC CONTROL PLAN (D1) ..... 6

HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1) ..... 7

HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1) ..... 12

FRICTION AGGREGATE (D1) ..... 14

TEMPORARY LIGHTING FOR SINGLE LANE STAGING ..... 17

ENGINEER’S FIELD OFFICE TYPE A (D1) ..... 21

TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1) ..... 22

RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL ..... 22

APPROACH SLAB REPAIR ..... 23

TEMPORARY INFORMATION SIGNING ..... 28

RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REPLACEMENT ..... 30

TEMPORARY TRAFFIC SIGNAL TIMING ..... 30

DEBRIS REMOVAL ..... 31

CLEANING AND PAINTING BEARINGS ..... 32

CLEANING AND PAINTING EXISTING STEEL STRUCTURES ..... 32

DECK SLAB REPAIR ..... 58

BRIDGE DECK LATEX CONCRETE OVERLAY ..... 64

STRUCTURAL REPAIR OF CONCRETE ..... 75

DIAMOND GRINDING AND SURFACE TESTING BRIDGE SECTIONS ..... 85

BRIDGE DECK GROOVING (LONGITUDINAL) ..... 90

BAR SPLICERS, HEADED REINFORCEMENT ..... 91

CEMENT, TYPE IL (BDE) ..... 92

COMPENSABLE DELAY COSTS (BDE) ..... 92

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) ..... 96

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... 98

HOT-MIX ASPHALT (BDE) ..... 108

PERFORMANCE GRADED ASPHALT BINDER (BDE) ..... 108

PORTLAND CEMENT CONCRETE (BDE) ..... 114

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be considered in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided above for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation duration must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies when necessary. The Department's contractor is responsible for contacting J.U.L.I.E. prior to all excavation work.

#### **TRAFFIC CONTROL PLAN (D1)**

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

#### **STANDARDS:**

**701201, 701301, 701311, 701901**

#### **DETAILS:**

Traffic Control and Protection for Side Roads, Intersections, and Driveways (TC-10)  
Typical Applications Raised Reflective Pavement Markers (Snow-Plow Resistant) (TC-11)  
Typical Pavement Markings (TC-13)  
Arterial Road Information Signing (TC-22)  
Driveway Entrance Signing (TC-26)

Revised 7/19/2024

**Method Of Measurement:**

Temporary Lighting for Single Lane Staging installed complete as specified and as indicated on the plans, shall be counted as lump sum for payment.

The contractor shall receive and accept the compensation as herein described; 50 percent of the total cost of this pay item shall be paid after the installation and approval by the Engineer of the complete Temporary Lighting, and the remaining 50 percent shall be paid after the removal once the project is completed.

All equipment and work provided by the Contractor including coordination, revisions, relocations, installation, maintenance, removal and restoration required to provide complete and operational Temporary Lighting for Single Lane Staging are included in the lump sum payment. The electric service installation, the electric utility service connection, and any associated material, labor, or charges to the utility company are included in the lump sum payment and will not be paid separately.

No extra compensation shall be paid to the Contractor for any incidental materials and labor required to fulfill the requirements as shown on the plans and specified herein.

**Basis Of Payment:**

This work will be paid for at the contract lump sum price for **TEMPORARY LIGHTING FOR SINGLE LANE STAGING**.

Revised 7/19/2024

**ENGINEER'S FIELD OFFICE TYPE A (D1)**

Effective: January 1, 2022

Revise the first paragraph of Article 670.02 to read:

**670.02 Engineer's Field Office Type A (D1).** Type A (D1) field offices shall have a ceiling height of not less than 7 feet and a floor space of not less than 1000 square feet with a minimum of two separate offices. The office shall also have a separate storage room capable of being locked for the storage of the nuclear measuring devices. The office shall be provided with sufficient heat, natural and artificial light, and air conditioning. Doors and windows shall be equipped with locks approved by the Engineer.

Add the following to Article 670.07 Basis of Payment.

The building or buildings, fully equipped, will be paid for at the contract unit price per calendar month or fraction thereof for ENGINEER'S FIELD OFFICE, TYPE A (D1).

Revised 7/19/2024