

MODEL: D:\a\h\k\p\c\alexburg\2\file\1213081\DOT - DIST 4 - PTB 2014-03\Work Order 08 - FY 2023 Slope Repair\1B_Transportation\Location_4\CADD_Sheets\003_005-ht-Summary_4.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				HENDERSON COUNTY								
				100% STATE								
				LOCATION #4								
				0005								
RURAL												
20100500	TREE REMOVAL, ACRES	ACRE	0.6	0.6								
20200100	EARTH EXCAVATION	CU YD	345	345								
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12	12								
20400800	FURNISHED EXCAVATION	CU YD	365	365								
20700110	POROUS GRANULAR EMBANKMENT	TON	17	17								
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	17	17								
28000400	PERIMETER EROSION BARRIER	FOOT	400	400								
28100207												
28100107	STONE RIPRAP, CLASS A4	TON	1752	1752								
28200200	FILTER FABRIC	SQ YD	2627	2627								
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	54	54								
44004250	PAVED SHOULDER REMOVAL	SQ YD	188	188								
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	49	49								
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	254	254								
50800105	REINFORCEMENT BARS	POUND	20	20								



KLINGNER & ASSOCIATES, P.C.
 Engineers • Architects • Surveyors
 616 N. 24TH ST. QUINCY, ILLINOIS 62301 217.223.3670
 STATE OF ILLINOIS DESIGN FIRM NO. 1842738

USER NAME = aschafer	DESIGNED -	REVISED -
PLOT SCALE = 40.0000 ' / in.	DRAWN -	REVISED -
PLOT DATE = 5/6/2024	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**F.A.S. ROUTE 1412 (IL 94)
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1412	106(SLP-S;CR-3)	HENDERSON	19	3
CONTRACT NO. 68H99			ILLINOIS FED. AID PROJECT	