

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	99 (I&2) RS-10	WILL	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

60A57

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	I-55 W. FRONTAGE RD.						
				I000-2A 100% STATE						
20201006	GRADING AND SHAPING SHOULDERS	UNIT	100	100						
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	44	44						
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1200	1200						
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	200	200						
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	655	655						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6						
40600300	AGGREGATE (PRIME COAT)	TON	28	28						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1						
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	141	141						
40600895	CONSTRUCTING TEST STRIP	EACH	3	3						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	261	261						
40600990	TEMPORARY RAMP	SQ YD	261	261						
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2888	2888						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	96	96						
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1140	1140						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	2511	2511						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	852	852						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	235	235						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1140	1140						
50300300	PROTECTIVE COAT	SQ YD	53	53						
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	235	235						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	990	990						
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	14780	14780						

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	I000-2A 100% STATE						
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	78	78						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	330	330						
X 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14780	14780						
X 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	78	78						
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	214	214						
XX006047	PULVERIZATION	SQ YD	11060	11060						

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

\* SPECIALTY ITEMS

PLOT DATE: 6/15/2007

6/15/2007 10:03:08 AM design-cad.dwg