F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
335	119R-2	LAKE	439	6
STA. 432+83.12		TO STA. 470+56.84		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

60B01

SUMMARY OF QUANTITIES

IDOT CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	1000-2A SAUNDERS RD / FIELD DR ROADWAY			J000-2A ROADWAY		X271-2A		Y007		Y030-1E LIGHTING		Y031-1F TRAFFIC SIGNALS									Y031-3D EMERGENCY VEHICLE PREEMPTION			Y032-1F
				CPOA (FIELD DR.)	OPUS (SAUNDERS RD.)	EDP	IL RTE 60/ I-94 RAMPS		IL RTE 60 BRIDGE		RETAINING WALL		IL RTE 60 & I-94 RAMPS/UNDERPASS		RIVERWOODS RD/BLVD				SAUNDERS RD / FIELD DR			I-94 RAMPS/ INTERCONNECT		RIVERWOODS RD/BLVD / I-94 SB RAMPS		SAUNDERS RD/ I-94 NB RAMPS	TRAFFIC SURVEILLANCE
				100% LAKE FOREST	100% LAKE FOREST	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	80% FEDERAL 20% STATE	100% ISTHA	100% METTAWA	100% LAKE COUNTY	80% FEDERAL 20% STATE	100% ISTHA	100% LAKE FOREST	80% FEDERAL 20% STATE	100% ISTHA	100% LIBERTY-VILLE F.D.	100% LINCOLN-SHIRE F.D.	100% LAKE FOREST	100% LAKE COUNTY
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	75	75																							
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	237				118.5	118.5																			
40601005	HOT-MIX ASPHALT REPLACMENT OVER PATCHES	TON	5				2.5	2.5																			
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2587	537	2050																						
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	654	199	455																						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX"D", N70	TON	322				161	161																			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	413				206.5	206.5																			
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	7681				3840.5	3840.5																			
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	26807			1238	12784.5	12784.5																			
42001300	PROTECTIVE COAT	SQ YD	40294	106	352	1527	19154.5	19154.5																			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	1004						502	502																	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	32				16	16																			
44000100	PAVEMENT REMOVAL	SQ YD	36302		1798	219	17142.5	17142.5																			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	2662				1331	1331																			
44000160	HOT-MIX ASPHALT SUFACE REMOVAL 2 3/4"	SQ YD	4038				2019	2019																			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	710	710																							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	81				40.5	40.5																			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	13486	585	45	984	5936	5936																			
44000700	APPROACH SLAB REMOVAL	SQ YD	303						151.5	151.5																	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	30				15	15																			
44002805	ISLAND REMOVAL	SQ FT	480	480																							
44003100	MEDIAN REMOVAL	SQ FT	10298				5149	5149																			
44004250	PAVED SHOULDER REMOVAL	SQ YD	3880				1940	1940																			
JI440010	CONCRETE MEDIAN BARRIER AND BASE REMOVAL	FOOT	197				98.5	98.5																			
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	260				130	130																			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	251				125.5	125.5																			
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	859				429.5	429.5																			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	3119				1559.5	1559.5																			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1						0.5	0.5																	
50105210	REMOVE EXISTING CULVERT	FOOT	38		38																						
50105220	PIPE CULVERT REMOVAL	FOOT	116				58	58																			
50157300	PROTECTIVE SHIELD	SQ YD	4384						2192	2192																	
50200100	STRUCTURE EXCAVATION	CU YD	3238						1359.5	1359.5	259.5	259.5															

* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

ILLINOIS RTE 60 OVER I-94

SUMMARY OF QUANTITIES
SHEET 2 OF 12

SCALE: NONE DRAWN BY: CBS

DATE: MAY 8, 2007 CHECKED BY: MPG