

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	49 BR-1	KANE	27	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE SFTY-2A				
X0325774	RELOCATE TEMPORARY IMPACT ATTENUATOR	EACH	2	2				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	2	2				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.5	0.5				
40600300	AGGREGATE (PRIME COAT)	TON	2	2				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	0.5	0.5				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	55	55				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	39	39				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	55	55				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	153.33	153.33				
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	30.67	30.67				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	600	600				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	12	12				
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1				
50300260	BRIDGE DECK GROOVING	SQ YD	324	324				
50300300	PROTECTIVE COAT	SQ YD	338	338				
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	2944	2944				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4350	4350				
50800515	BAR SPLICERS	EACH	71	71				
50901050	STEEL RAILING, TYPE SM	FOOT	128	128				
51500100	NAME PLATES	EACH	1	1				
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	1.8	1.8				
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	3	3				
* 63300230	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	75	75				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1				
70300500	PAVEMENT MARKING TAPE, TYPE III	FOOT	800	800				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE SFTY-2A				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	636	636				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	636	636				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	550	550				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	10	10				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	152	152				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12				
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4				
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16	16				
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1				
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1				
* 81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	100	100				
* 81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1100	1100				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100	100				
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	7	7				
* 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	1	1				
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	7	7				
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	7	7				
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	7	7				
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1				
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3	3				
58700300	CONCRETE SEALER	SQ FT	865.3	865.3				
* X0323115	REFLECTOR MARKERS, TYPE A	EACH	4	4				
* X0323116	REFLECTOR MARKERS, TYPE B	EACH	9	9				
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	2.5	2.5				

\*SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	

6/18/2007 2:48:21 PM C:\PROJECTS\60881\60881.DWG